



DELHI DEVELOPMENT AUTHORITY
OFFICE OF THE EXECUTIVE ENGINEER ELECT. DIV-2
19TH FLOOR, VIKAS MINAR, I.P ESTATE, NEW DELHI-110002
Email ID: eeeld2@dda.org.in
Tel: 011-23378290 (O)

F No. F2 (13)/EE/ELD-2/DDA/2025-26/586

Dated: 13/10/2025

Notice Inviting Quotation No.-03/EE/ELD-2/DDA/2025-26

Sealed quotations are invited from eligible and reputed firms/vendors/Contractors etc. by Executive Engineer/ELD-2 on behalf of DELHI DEVELOPMENT AUTHORITY for the works as mentioned herein below. The quotations must be submitted on or before 16.10.2025 up to 03:00 PM in the office of EE/ELD-2 and same shall be opened on the same day at 03:30 PM. Incomplete quotations shall be summarily rejected.

Name of work: Running and maintenance of DDA Roshanara Club,
SH: Additional Work of Fire Fighting System and Fire Alarm System at DDA Roshanara Club.

Estimated Cost: Rs. 3,21,539.00

S. No.	Description of Item	Qty.	Unit	Quoted Rate (in Rs)	Amount (in Rs)
1.00	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 1239/Class -II of IS: 3589 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required :				
1.01	80mm dia.	12	Meter		
2.00	Supplying and fixing Single headed external yard hydrant valve with 1 No. 63 mm dia instantaneous FM Gunmetal/Stainless Steel coupling and cast iron wheel, ISI marked, conforming to IS 5290 (type A) with blank Gunmetal/Stainless Steel cap and chain as required :				

2.01	Single headed Stainless steel	1	Each		
3.00	Supplying and fixing 63 mm dia, 15 m long RRL hose pipe with 63 mm dia male and female couplings duly bound with GI wire, rivets etc. conforming to IS 636 (type-A) as required :				
3.01	Stainless Steel (Grade 304)	2	Each		
4.00	Supplying & fixing 63 mm dia gun metal short branch pipe with 20 mm nominal internal diameter size nozzle conforming to IS 903 suitable for instantaneous connection to interconnect hose pipe coupling as required:				
4.01	Stainless Steel (Grade 304)	1	Each		
5.00	Supplying and fixing External Hydrant hose cabinet to accommodate the hose, pipes, branch pipe nozzle and the hydrant outlets. The double door cabinet is made up of LFRP sheet with glass fronted hinged centre opening glazed doors and lock, painted with scarlet red colour including providing of masonry or MS frame structure.				
5.01	Size :- 750mm X 600mm X 250mm	1	Each		
6.00	Supplying, installation, testing & commissioning sector panel suitable for following zones, complete with visual indications for short circuit fault, open circuit fault, fire condition and all other standard facilities as per IS:2189 with mimic diagram for all area/zone covered, complete with all connections, interconnections as required.				
6.01	4 Zone	1	Each		
7.00	Supplying, installation, testing & commissioning of heat detector operating at 54°C/57°C with rate of rise cum fixed temperature (dual thermistor) type with mounting base	20	Each		

	complete with all connection etc. as required.				
8.00	Supplying, installation, testing & commissioning fire alarm sounder with facility to make announcement, mounted in M.S. box (16 SWG) with hinged cover plate & suitable for operation with amplifier i/c line matching transformer etc. complete as required.	3	Each		
9.00	Supplying, installation, testing & commissioning of manual call boxes of MS construction in surface/recess with stainless steel chain & hammer assembly complete with glass and push button etc. as required.	3	Each		
10.00	Supplying & laying of 2x1.5 sqmm fire alarm armoured cable, 600/1000V rated with annealed copper conductor having XLPE insulation, steel wire armouring & FRLS/HFFR outer sheath complete as required.	500	Meter		
11.00	Supply, Installation Testing & Commissioning of Self illuminating photo luminescent type fire instruction signage of size 12 Inch x 9 Inch in Red/ Green color 2mm Acrylic sheet, including mounting arrangement on ceiling wall complete as required	30	Each		
12.00	Providing and supplying MS Angle Terrace Pump Shed framing consists of L-shaped mild steel (MS) angles sizes for the frame include 50x50x5mm angle with cover is typically made from corrugated MESH MASTERS PVC Gate Sheet. A protective to provide corrosion and weather resistance. The frame members are usually welded together, and galvanized fasteners are used to secure the roofing sheets.	2	Job		
13.00	Supplying, installation, testing & commissioning of Battery operated smoke detectors with rechargeable battery etc complete as required.	11	Each		

14.00	Supplying Erection Testing & Commissioning of wall mounted cubicle panel with locking arrangement fabricated out of 2mm thick CRCA Sheet duly wired with suitable rating of stranded PVC insulated copper conductor single core cable to MCB with cable lugs & duly spray painted with Inter connections and complete with following accessories etc. complete as required :- Incomer 1. Main DPMCB 63AMP :- 01 No. 2. NO-NC Contactor With Relay 10Amp :- 3 Nos. 3. ON/OFF Indicating Lamp :- 3 Nos. 4. Auto/ Manual Selector Switch :- 01 No. 5. Single Pole MCB 6AMP :- 3 Nos. 6. DC Transformer :- 01 No.	1	Each		
	Total				
	Total in words				

Signed copy of following documents are required to be submitted along with the quotations in a sealed envelope superscribed as "Quotation for Additional Work of Fire Fighting System and Fire Alarm System at DDA Roshanara Club." and addressed to the **Executive Engineer (E)/ELD-2/DDA, Vikas Minar:-**

1. Copy of PAN Card of Agency/Contractor/Firm/Vendor etc.
2. Copy of GST Registration.
3. Bank Account details.
4. Earnest Money: Not applicable.
5. Self-declaration/undertaking on agency's letter head stating that our firm/agency is not currently blacklisted or debarred from participating in tenders by any Government or public sector entity.
6. Intending quotationers should have experience of execution of similar work (during the last 07 years) for "**SITC of Fire Fighting & Fire Alarm system**". Signed copy of the supporting document may be submitted with quotations. Decision of EE- in-charge in this regard shall be final and binding on the quotationers.

Criteria :- Three or more similar nature of works each costing not less than 40% of the estimated cost put to quotation or two similar work each costing not less than 60% of the estimated cost put to quotation or one similar work costing not less than 80% of the estimated cost put to quotation.

General Terms and Conditions:

1. The work shall be carried out as per relevant electrical specifications and to the entire satisfaction of the Engineer-in-charge of the work.
2. The intending quotationers are advised to inspect and assess the site of work and satisfy themselves before submission of quotations and no extra payment shall be entertained.
3. No T & P/Labour/cartage will be provided by the Department.
4. Department will provide only electricity for execution of this work.
5. The payment will be made only on satisfactory completion of work.
6. The quoted rates should be inclusive of all applicable taxes, duties, GST etc. and nothing extra shall be paid on this account.
7. The work may be carried out to integrate with the existing system at site.
8. The contractor has to stands guarantee/warranty for a period of 6 months from date of completion against unsatisfactory performance of the system, defect in the materials provided by him etc.
9. Time allowed for completing the work is 10 days.
10. Dismantle material, if any, shall be retained with the contractor and shall be removed from site by him at his own cost immediately after work completion.
11. No advance payment will be made to the agency.
12. EE/ELD-2 reserves the right to accept or reject any quotations without assigning any reason.
13. Department will not be responsible for any loss/ theft/ damage caused at site/ surrounding, the same shall be made good within the quoted rates.
14. The agency will require to assist during inspection of DFS team for fire NOC. Nothing extra shall be paid on this account.

LIST OF ACCEPTABLE MAKES

S.No.	Detail of Materials	Manufacturer's Name
1.	MS Pipe (C- Class)	Jindal (Hissar) / Parkash Surya / TATA
2.	Yard Hydrant Valve	LIFEGUARD/NEWAGE/SAFEX/SAFEGUARD
3.	RRL Hose Pipe/Short Branch pipe	LIFEGUARD/NEWAGE/SAFEX/SAFEGUARD
4.	Sector Panel/Heat Detector/Hooter/Manual Call Box	AGNI DEVICE/AGNI INSTRUMENT
5.	FRLS Cu. Control Cables/Wires/ fire survival cable.	Havells/KEI/Asian/Universal/Polyacab/ RR kabel/ Rallison/ HPL Bonton/ Skytone
6.	LED Signage	Autolite/ Prolite/ Fast Sign System/ Glowline/ ASES.
7.	Control Panel accessories	Legrand /Schneider /Hager / Siemens/ ABB/ L & T.
8.	Any other item	As per Engineer-in-Charge

Ashok
13/10/25

Ashok Kumar
Executive Engineer (E)
ELD-2/DDA

Copy to:-

1. SE (E)/Sports DDA for kind information please.
2. Director (System), DDA through email ddatender@dda.org.in with request to publish this NIQ on DDA website.
3. Secretary (DRC) for kind information please.
4. AE (E)-III& IV/ELD-2 DDA.
5. Notice Board (Vikas Minar), DDA.

Executive Engineer (E)
ELD-2/DDA

