

दिल्ली विकास प्राधिकरण
अधिशायी अभियंता का कार्यालय
स्पोर्ट्स मैनेजमेंट सेल
1 मंजिल, स्क्वैश और बैडमिंटन स्टेडियम,
सिरी फोर्ट रोड, नई दिल्ली -110049 ईमेल: eesmc@dda.org.in

No.F.4(181)EE/SMC/DDA/2026-27/ 179

Date : 11/08/26

To

M/s Arun Sharma
H.No. A 1 -168, Main 30 feet Road,
Prem Vihar, Shiv Vihar, Karawal Nagar
North East Delhi, Delhi-110094.

NOW:- M/o Various Sports Complexes/Golf Courses (A/R & M/O of works at Rohini Sports Complex for the year 2026-27).

SH:- Installation of Protective Shed for Newly Installed Water Cooler and RO System at Various Sports Complexes & Replacement of yogashed Roof with Polycarbonated sheet and miscellaneous work at RSC.

Ref:- Performance guarantee in the form of FDR A/C No: 610856110001235 issued dated 04.08.2026 for Rs. 2,56,965/- of Bank of India, C -2 Mukhiya Market, Karawal Nagar Branch, Delhi-110094.

Sir,

Your Percentage rate tender for the above-mentioned work has been accepted on behalf of the Delhi Development Authority as per the rates and conditions given below.

नीचे दी गई प्रतिशत दरों और शर्तों के अनुसार, दिल्ली विकास प्राधिकरण की तरफ से उपर्युक्त कार्य के लिए आपकी प्रतिशत दर निविदा स्वीकार करली गई है।

- | | | |
|--|---|--|
| 1. Estt. Cost/अनुमानितलागत | : | Rs. 21,85,073/-
(Rupees Twenty one lakh eighty five thousand seventy three only).
(रुपये इक्कीस लाख पचासी हजार और तिहत्तर केवल) |
| 2. Tender Amount
/स्वीकृतनिविदाराशि | : | Rs.16,00,347.68/-
(Rupees Sixteen lakh three hundred forty seven and sixty eight paisa only)
(रुपये सोलह लाख तीन सौ सैंतालीस और पैसा अड़सठ केवल) |
| 3. Percentage/प्रतिशत | : | 26.76% Below the estimated cost |
| 4. Time allowed/ समयकीअनुमति | : | 60 days (दिन) |

You are requested to contact AE-V/SMC for taking possession of the site & start the work. You are also requested to attend this office along with non-judicial stamp paper worth Rs. 100/- to sign to complete the formal agreement within 7 days from the date of this letter.

आपसे अनुरोध है कि साइट पर कब्जा करने और काम शुरू करने के लिए सहायक अभियंता-V/ एसएमसी से संपर्क करें। आपसे यह भी अनुरोध है कि आपको इस कार्यालय में इस पत्र के जारी होने की तारीख से 7 दिनों के भीतर गैर-न्यायिक 100रु/- के स्टैप पेपर के साथ-साथ औपचारिक समझौते पर हस्ताक्षर करने हैं।

Contd.2

Please note that the time allowed for carrying out the work will be reckoned from the 10th day after the date of issue of this letter to commence the work. Further if you fail to commence the work as specified above, the award letter will be withdrawn by DDA without prejudice to any other right or remedy available on law will be at liberty to forfeit the Earnest Money and performance guarantee absolutely.

कृपया ध्यान दें कि काम करने के लिए अनुमति के समय को काम शुरू करने के लिए इस पत्र के जारी होने की तारीख के 10 दिन के बाद से गिना जाएगा। इसके अलावा यदि आप ऊपर निर्दिष्ट कार्य शुरू करने में असफल हो जाते हैं, तो डीडीए द्वारा किसी भी अन्य अधिकार या कानून पर उपलब्ध उपायों के लिए पूर्वाग्रह से वापस ले लिया जाएगा अग्रिम धन राशि और प्रदर्शन गारंटी को पूरी तरह से ज़ब्त करने के लिए स्वतंत्र होगा।

अधिशायी अभियंता
एसएमसी/डीडीए

Copy to (प्रतिलिपि): -

1. Chief Engineer (Sports)DDA
मुख्य अभियंता (खेल) डीडीए
2. Project Director - II (Sports)/DDA.
परियोजना निदेशक - II (खेल) / डीडीए
3. Director (System) DDA for display at DDA website E-mail at doc or pdf & (ddatender@dda.org.in)
निदेशक (सिस्टम) डीडीए
4. Secy/ RSC /DDA.
सचिव / आरएससी / डीडीए
5. Labour Commissioner, Rajpura Road, New Delhi.
श्रम आयुक्त, राजपुरा रोड, नई दिल्ली
6. Delhi Contractors Building association (Regd) No. 5503 Ch. Bhim Singh Road, Delhi (Ch. Prem Raj Bhawan New Chandrawal Road (UPC).
दिल्ली के ठेकेदार बिल्डिंग एसोसिएशन (पंजीकरण) सं। 5503 चा।भीम सिंह रोड, दिल्ली (चौ प्रेम राज भवन नई चंद्रावल रोड (यूपीसी)
7. Delhi Contractors Welfare Association (Regd) 306, Masjid Moth, South Extn. Part-II, New Delhi-110049 (UPC).
दिल्ली कन्स्ट्रक्टर्स वेलफेयर एसोसिएशन (रजिड) 306, मस्जिद मॉथ, दक्षिण विस्तार भाग- II, नई दिल्ली -110049 (यूपीसी)
8. Indian Contractor Association (Regd) G-80/20, Main Bazar Laxmi Nagar, Delhi-110092 (UPC).
भारतीय ठेकेदार एसोसिएशन (रजिड) जी -80 / 20, मुख्य बाजार लक्ष्मी नगर, दिल्ली -110092 (यूपीसी)।
9. Assistant Engineer-V /SMC /DDA for information alongwith copy of schedule of quantities.
जानकारी के लिए सहायक अभियंता-V / एसएमसी डीडीए, मात्रा के अनुसूची की प्रति के साथ।
10. Head Clerk SMC/ DDA. He is requested to issue the Master Register at once.
हेड क्लर्क एसएमसी/डीडीए उन्हें एक बार में मास्टर रजिस्टर जारी करने का अनुरोध किया जाता है।
11. Accountant/SMC/ DDA.
लेखाकार/एसएमसी / डीडीए
12. Copy of agreement.
समझौते की प्रतिलिपि

अधिशायी अभियंता
एसएमसी/डीडीए

Percentage Boq

Tender Inviting Authority: Executive Engineer/Sports Management Cell

Name of work: M/o Various Sports Complexes/Golf Courses (AR & MO of works at Rohini Sports Complex for the year 2026-27)

Sub Head: Installation of Protective Shield for Newly Installed Water Cooler and RO System at Various Sports Complexes & Replacement of yogashed Roof with Polycarbonated sheet and miscellaneous work at RSC.

Estimated Cost : Rs. 21,85,073/-

NIT No: 11/NIT/IAE/PEES/MC/DN/2026-27


Name of the Bidder/ Bidding Firm / Company
Arun Sharma

PRICE SCHEDULE

(This Boq to be updated must not be modified/ replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1 00	Excavating holes more than 0.30 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 30cm in depth, including consolidating each deposited layer by ramming, watering etc. disposing of surplus excavated soil as directed within a haul of 50 m and lift upto 1.5 m	20.00	each	82.45	1649.00	INR One Thousand Six Hundred Forty Nine & Paise Zero Only
2 00	1.2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	2.50	cum	7878.50	19696.25	INR Nineteen Thousand Six Hundred Ninety Six & Paise Twenty Five Only
3 00	9/4 cement concrete - all works upto plinth level 1.5-10 (1 cement : 5 coarse sand derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	0.50	cum	6518.60	3259.30	INR Three Thousand Two Hundred Fifty Nine & Paise Thirty Only
4 00	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns.	24.00	sqm	392.15	9411.60	INR Nine Thousand Four Hundred Eleven & Paise Sixty Only
5 00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.), trusses etc., including cutting, hoisting, fitting in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete. Hot finished welded type tubes.	647.91	kg	194.40	125953.70	INR One Lakh Twenty Five Thousand Nine Hundred Fifty Three & Paise Seventy Only
6 00	Providing and fixing stainless steel (Grade 304) railing made of hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete. i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of wall slab with suitable arrangement as per approval of Engineer-in-Charge. (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	781.21	kg	772.40	603406.60	INR Six Lakh Three Thousand Four Hundred Six & Paise Sixty Only
7 00	Providing & fixing UV stabilized fibreglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated T or U bolts, bolts & of nuts 8 mm dia. G.I plain/bushen washers complete but excluding the cost of purfins, rafters, trusses etc. The sheets shall be manufactured out 2400 TEG panel (ovg), incorporating minimum 0.3% ultra-violet stabilizer in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.	29.70	sqm	1245.66	36996.10	INR Thirty Six Thousand Nine Hundred Ninety Six & Paise Ten Only
8 00	Painting with synthetic enamel paint of approved brand and manufacturer required colour to give an even shade two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacturer	30.05	sqm	226.25	6798.81	INR Six Thousand Seven Hundred Ninety Eight & Paise Eighty One Only
9 00	Painting with synthetic enamel paint of approved brand and manufacturer of required colour to give an even shade one or more coats on old work	252.85	sqm	102.80	25992.98	INR Twenty Five Thousand Nine Hundred Ninety Two & Paise Ninety Eight Only
10 00	Demolishing thatch roofing including m/s, bamboo, puffer etc. complete including stacking of serviceable material and disposal of unworkable material within 50 meters haul	531.04	sqm	57.70	30641.01	INR Thirty Thousand Six Hundred Forty One & Paise Zero One Only
11 00	Providing, erecting, laying and fixing in position in 3 to 6 mm thick bamboo mat corrugated sheet (BACS) as per IS 15476:2004 in roofing with self drilling screws along with EPDM washers complete or with galvanized iron 1 or 1.5 hooks 8 mm dia G.I. plain and bushen washers etc., all complete as per direction of Engineer-in-Charge	34.50	sqm	6012.10	207417.45	INR Two Lakh Seven Thousand Four Hundred Seventeen & Paise Forty Five Only

12.00	Providing and fixing in position ridges of 3.5 to 4 mm thick bamboo mat ridge cap (BMC) as per IS: 13475-2004 in roofing with self drilling screws along with EPDM washers complete or with galvanized iron J or L hooks 8 mm dia G.I. plain and bitumen washers etc, all complete as per direction of Engineer-in-Charge.	11.50	metre	4830.10	55546.15	INR Fifty Five Thousand Five Hundred Forty Six & Paise Fifteen Only
13.00	Providing & fixing Green or similar coloured, 3mm thick high impact solid polycarbonated sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts, 8mm dia. G.I. plain and bitumen washers or with self drilling fasteners and EPDM washers etc, complete but excluding the cost of puling, rafters, trusses etc including cutting sheets to size and shape wherever required and as direction of Engineer in Charge. Note: (The polycarbonated sheet shall be compact solid sheet and not the Multi wall/hollow sheet).	531.04	sqm	2107.07	1118938.45	INR Eleven Lakh Eighteen Thousand Nine Hundred Thirty Eight & Paise Forty Five Only
14.00	Less GST correction factor 0.027 on DSR items	1.00	nos	60034.10	-60034.10	INR Minus Sixty Thousand Six Hundred Thirty Four & Paise Ten Only
Total in Figures					2185073.30	INR Twenty One Lakh Eighty Five Thousand Seventy Three & Paise Thirty Only
Quoted Rate in Figures					1600347.68	INR Sixteen Lakh Three Hundred Forty Seven & Paise Sixty Eight Only
Quoted Rate in Words					INR Sixteen Lakh Three Hundred Forty Seven & Paise Sixty Eight Only	


 अधिशासी अभियन्ता
 खेल प्रबंधन प्रकौष्ठ
 सिरि फोर्ट नई दिल्ली-110049