



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092
E-mail: eehcdx@gmail.com

No. F.1 (311)2025-26/EE/HCD-10/A/DDA/60

Date: 14-5-2026

To,

Sh. Rahul Suryavanshi,
D-368, Ganesh Nagar,
Pandav Nagar Complex,
Delhi-110092,
E-mail: rahulsuryavanshi92@gamil.com

Name of work : M/o Completed Scheme under NA-II (Hort Zone)
SH : Annual maintenance of Civil Work at Golden Jubilee park.
E-tender ID : 2026_DDA_900354_1
NIT No. : 32/EE/HCD-10/DDA/2025-26 (16/EE(P)/HCC-3/DDA/2025-26)
Estimated cost: Rs 45,87,516/-
Earnest money: Rs 91,750/-
Time Allow : 365 Days
Ref : P.G. submitted in shape of FDR A/c No. 45170191017 dt. 11.05.2026
sum of Rs 8,19,790/-

Dear Sir,

Your percentage rate tender for the above-mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rates subject to following terms & condition:-

1.	Estimated Cost	Rs. 45,87,516/- (Rupees Forty Five Lakh Eighty Seven Thousand Five Hundred Sixteen Only)
2.	Quoted & Accepted Rate (Contractor's Enhancement)	@(-) 32.87 % (Thirty Two Point Eight Seven) below on estimated cost
3.	Quoted Tender Amount	Rs. 30,79,599.49 (Rupees Thirty Lakh Seventy Nine Thousand Five Hundred Ninety Nine and Paise Forty Nine Only)
4.	Accepted Tender Amount	Rs. 30,79,599/- (Rupees Thirty Lakh Seventy Nine Thousand Five Hundred Ninety Nine Only)

Note: The payment of bills shall be released only after verification of FDR submitted against PG.


Time allowed for carrying out the work shall **365 Days** only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 3 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from next day after the date of issue of this letter to commence the work. You are requested to contact A.E.- V/HCD-10/DDA of this division and start the work immediately.

Thanking you,

Yours faithfully


(Sandeep Kushwana)
Executive Engineer
HCD-10/D.D.A.

Copy to :-

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE- V/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. DDA's Website.
19. Agreement copy.

Executive Engineer
HCD-10/D.D.A.

Validate Print Help

Tender Inviting Authority: Delhi Development Authority
Name of Work: M/o completed scheme under NA-II Hort. Zone.
SH:- Annual maintenance of civil work at Golden Jubilee Park.

NIT No: 16/EE(PJ)/HCC-3/DDA/2025-26
32/EE/HCD-10/DDA/2025-26

Name of the Bidder/
Bidding Firm / RAHUL SURYAVANSHI

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER Estimated Rate in Rs. P	NUMBER # TOTAL AMOUNT in Rs. P	TEXT # TOTAL AMOUNT In Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	100	cum	260.3	26030	INR Twenty Six Thousand & Thirty Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	40	cum	7878.5	315140	INR Three Lakh Fifteen Thousand One Hundred & Forty Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	30	cum	6518.6	195558	INR One Lakh Ninety Five Thousand Five Hundred & Fifty Eight Only
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	100	sqm	155.9	15590	INR Fifteen Thousand Five Hundred & Ninety Only
5	Providing and fixing 10x10x7.50 cm Granite stone block hand cut and chisel dressed on top, for paving in floors, drains etc. laid over 20mm thick base mortar 1:4 (1 cement : 4 coarse sand) with joints 10mm wide filled with same mortar including ruled pointing etc. complete as per direction of engineer-in-charge.	30	sqm	2189.15	65675	INR Sixty Five Thousand Six Hundred & Seventy Five Only
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	10	cum	7132.25	71323	INR Seventy One Thousand Three Hundred & Twenty Three Only
7	Hiring and deployment of Hydraulic Excavator (3D) with driver and fuel all complete as per direction of Engineer-in-charge.	25	Day	11167.7	279193	INR Two Lakh Seventy Nine Thousand One Hundred & Ninety Three Only

You are requested to attend this office for drawing formal agreement along with a non-
Rs. 100/- (Rs. One hundred only) which shall be brought by you within 3

8	Hiring and deployment of Tractor with trolley with driver and fuel all complete as per direction of Engineer-in-charge.	50	Day	1920.55	96028	INR Ninety Six Thousand & Twenty Only
9	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	10	cum	10117.6	101176	INR One Lakh One Thousand One Hundred & Seventy Six Only
10	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	300	metre	39.35	11805	INR Eleven Thousand Eight Hundred & Five Only
11	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	150	metre	109.45	16418	INR Sixteen Thousand Four Hundred & Eighteen Only
12	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc).	500	kg	772.4	386200	INR Three Lakh Eighty Six Thousand Two Hundred Only
13	Lettering with black Japan paint of approved brand and manufacture	6250	per letter per cm height	6.15	38438	INR Thirty Eight Thousand Four Hundred & Thirty Eight Only
14	Supplying at site :R.C.C. Standards post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarsesand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6 mm bar ribs wherever required as per direction of Engineer-in-charge (cost of earth works in excavation, concrete works in foundation to be paid separately).	40	cum	32891.2	1315648	INR Thirteen Lakh Fifteen Thousand Six Hundred & Forty Eight Only

15	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire	22848	metre	14	319872	INR Three Lakh Nineteen Thousand Eight Hundred & Seventy Two Only
16	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5 mm thick) wire of high tensile strength of 165 kg/ sq. mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	200	metre	375.8	75160	INR Seventy Five Thousand One Hundred & Sixty Only
17	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	200	sqm	102.8	20560	INR Twenty Thousand Five Hundred & Sixty Only
18	Cutting bajri paths and making good the same including supply of extra quantities of brick aggregate, required	200	sqm	270.2	54040	INR Fifty Four Thousand & Forty Only
19	Welding by gas or electric plant including transportation of plant at site etc. complete.	2000	cm	3.7	7400	INR Seven Thousand Four Hundred Only
20	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	100	sqm	333.35	33335	INR Thirty Three Thousand Three Hundred & Thirty Five Only
21	Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge. (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment). Overhead informatory road signage	50	sqm	5879.9	293995	INR Two Lakh Ninety Three Thousand Nine Hundred & Ninety Five Only

22	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I S 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	80	sqm	1623.05	129844	INR One Lakh Twenty Nine Thousand Eight Hundred & Forty Four Only
23	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50 mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge. 60 mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.	250	sqm	1045.65	261413	INR Two Lakh Sixty One Thousand Four Hundred & Thirteen Only
24	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	2500	kg	117.35	293375	INR Two Lakh Ninety Three Thousand Three Hundred & Seventy Five Only
25	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	1500	kg	194.4	291600	INR Two Lakh Ninety One Thousand Six Hundred Only
Add Correction factor (0.973)						
Total in Figures					4587516.00	INR Forty Five Lakh Eighty Seven Thousand Five Hundred & Sixteen Only
Quoted Rate in Figures						
					Less (-)	32.87%
					3079599.49	INR Thirty Lakh Seventy Nine Thousand Five Hundred & Ninety Nine and Paise Forty Nine Only
Quoted Rate in Words					INR Thirty Lakh Seventy Nine Thousand Five Hundred & Ninety Nine and Paise Forty Nine Only	


 Executive Engineer / 26
 HCD-10/DDA



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092

No. F.1 (312)2025-26/EE/HCD-10/A/DDA/ 58

Date: 14-5-2026

To,

✓ Sh. Rahul Suryavanshi,
D-368, Ganesh Nagar,
Pandav Nagar Complex,
Delhi-110092,
E-mail: rahulsuryavanshi92@gamil.com

Name of work: M/o Northern Ridge KNR.
SH : Annual maintenance of civil works at Kamla Nehru Ridge (The Northern Ridge)
E-tender ID : 2026_DDA_900355_1
NIT No. : 33/EE/HCD-10/DDA/2025-26 (17/EE(P)/HCC-3/DDA/2025-26)
Estimated cost: Rs 51,99,334/-
Earnest money: Rs 1,03,987/-
Time Allow : 365 Days
Ref : P.G. submitted in shape of FDR A/c No. 45170422955 dt. 11.05.2026
sum of **Rs 9,83,195/-**

Dear Sir,

Your percentage rate tender for the above-mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rates subject to following terms & condition:-

1.	Estimated Cost	Rs. 51,99,334/- (Rupees Fifty One Lakh Ninety Nine Thousand Three Hundred Thirty Four Only)
2.	Quoted & Accepted Rate (Contractor's Enhancement)	@ (-) 33.91 % (Thirty Three Point Nine One) below on estimated cost
3.	Quoted Tender Amount	Rs. 34,36,239.84 (Rupees Thirty Four Lakh Thirty Six Thousand Two Hundred Thirty Nine and Paise Eighty Four Only)
4.	Accepted Tender Amount	Rs. 34,36,239/- (Rupees Thirty Four Lakh Thirty Six Thousand Two Hundred Thirty Nine Only)

Note: The payment of bills shall be released only after verification of FDR submitted against PG.


Time allowed for carrying out the work shall **365 Days** only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 3 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from next day after the date of issue of this letter to commence the work. You are requested to contact A.E.-V/HCD-10/DDA of this division and start the work immediately.


Thanking you,

Yours faithfully


(Sandeep Kushwaha)
Executive Engineer
HCD-10/D.D.A.

Copy to :-

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association,11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth,Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE- V/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. DDA's Website.
19. Agreement copy.


**Executive Engineer
HCD-10/D.D.A.**

Tender Inviting Authority: Delhi Development Authority

Name of Work: M/o Northern Ridge KNR.

SH:- Annual maintenance of civil works at Kamla Nehru Ridge (The Northern Ridge).

NIT No: 17/EE(P)/HCC-3/DDA/2025-26
33/EE/HCD-10/DDA/2025-26

Name of the Bidder/ Bidding Firm /	RAHUL SURYAVANSHI
---------------------------------------	-------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	80.00	cum	260.30	20824	INR Twenty Thousand Eight Hundred & Twenty Four Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	30.00	cum	7878.50	236355	INR Two Lakh Thirty Six Thousand Three Hundred & Fifty Five Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	25.00	cum	6518.60	162965	INR One Lakh Sixty Two Thousand Nine Hundred & Sixty Five Only
4	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	2500.00	kg	117.35	293375	INR Two Lakh Ninety Three Thousand Three Hundred & Seventy Five Only
5	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	1500.00	Kg	772.40	1158600	INR Eleven Lakh Fifty Eight Thousand Six Hundred Only

6	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete	80.00	sqm	2354.70	188376	INR One Lakh Eighty Eight Thousand Hundred & Seventy Six Only
7	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	150.00	sqm	1948.25	292238	INR Two Lakh Ninety Two Thousand Two Hundred & Thirty Eight Only
8	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	200.00	sqm	738.65	147730	INR One Lakh Forty Seven Thousand Seven Hundred & Thirty Only
9	Providing and fixing ISI marked oxidised M.S. lower bolt black finish, (Barrel type) with necessary screws etc. complete (Copper oxidised as per IS 1378) 200x10 mm	50.00	No,s	69.40	3470	INR Three Thousand Four Hundred & Seventy Only
10	Welding by gas or electric plant including transportation of plant at site etc. complete.	2500.00	cm	3.70	9250	INR Nine Thousand Two Hundred & Fifty Only
11	40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand) with joints finished flush. a)Red sand stone	150.00	sqm	1280.10	192015	INR One Lakh Ninety Two Thousand & Fifteen Only
12	Supplying and stacking at site. Good earth	100.00	cum	775.50	77550	INR Seventy Seven Thousand Five Hundred & Fifty Only
13	Supplying and stacking at site. Red bajri	100.00	cum	1564.90	156490	INR One Lakh Fifty Six Thousand Four Hundred & Ninety Only
14	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	250.00	sqm	155.90	38975	INR Thirty Eight Thousand Nine Hundred & Seventy Five Only
15	Providing and fixing 10x10x7.50 cm Granite stone block hand cut and chisel dressed on top, for paving in floors, drains etc. laid over 20mm thick base mortar 1:4 (1 cement : 4 coarse sand) with joints 10mm wide filled with same mortar including ruled pointing etc. complete as per direction of engineer-in-charge.	50.00	sqm	2189.15	109458	INR One Lakh Nine Thousand Four Hundred & Fifty Eight Only
16	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS :12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	10000.00	litre	11.00	110000	INR One Lakh Ten Thousand Only

17 Brick edging in full disposal of surplus modular brick

18 Laiterng

19

20

17	Brick edging in full brick width and half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	450.00	metre	194.30	87435	INR Eighty Seven Thousand Four Hundred & Thirty Five Only
18	Lettering with black Japan paint of approved brand and manufacture	12500.00	per letter per cm height	6.15	76875	INR Seventy Six Thousand Eight Hundred & Seventy Five Only
19	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	240.00	cum	196.00	47040	INR Forty Seven Thousand & Forty Only
20	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall 20 mm dia nominal bore	80.00	metre	437.30	34984	INR Thirty Four Thousand Nine Hundred & Eighty Four Only
21	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall 25 mm dia nominal bore	80.00	metre	551.70	44136	INR Forty Four Thousand One Hundred & Thirty Six Only
22	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall 32 mm dia nominal bore	100.00	metre	667.00	66700	INR Sixty Six Thousand Seven Hundred Only
23	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall 40 mm dia nominal bore	100.00	metre	811.90	81190	INR Eighty One Thousand One Hundred & Ninety Only
24	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall 50 mm dia nominal bore	100.00	metre	1048.35	104835	INR One Lakh Four Thousand Eight Hundred & Thirty Five Only
25	Hiring and deployment of Hydraulic Excavator (3D) with driver and fuel all complete as per directions of Engineer-in-charge.	20.00	per day	11167.70	223354	INR Two Lakh Twenty Three Thousand Three Hundred & Fifty Four Only
26	Hiring and deployment of Tractor with trolley ic driver and fuel all complete as per directions of Engineer-in-charge.	40.00	per day	1920.55	76822	INR Seventy Six Thousand Eight Hundred & Twenty Two Only
27	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :a) One or more coats on old work	300.00	sqm	102.80	30840	INR Thirty Thousand Eight Hundred & Forty Only
28	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. a) Hot finished welded type tubes	3000.00	kg	194.40	583200	INR Five Lakh Eighty Three Thousand Two Hundred Only
29	Providing and fixing brass stop cock of approved quality :20 mm nominal bore	50.00	each	379.20	18960	INR Eighteen Thousand Nine Hundred & Sixty Only

30	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	20.00	cum	7132.25	142645	INR One Lakh Forty Two Thousand Hundred & Forty Five Only
31	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	5.00	cum	9105.95	45530	INR Forty Five Thousand Five Hundred & Thirty Only
32	12 mm cement plaster of mix : a) 1:6 (1 cement: 6 fine sand)	100.00	sqm	333.35	33335	INR Thirty Three Thousand Three Hundred & Thirty Five Only
33	Finishing walls with water proofing cement paint of required shade :a) New work (Two or more coats applied @ 3.84 kg/10 sqm)	100.00	sqm	116.90	11690	INR Eleven Thousand Six Hundred & Ninety Only
34	Finishing walls with water proofing cement paint of required shade :a) Old work (one or more coats @ 2.20 kg/10 sqm) complete.	200.00	sqm	75.80	15160	INR Fifteen Thousand One Hundred & Sixty Only
35	Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeling conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2007 in silver white with blue colour back ground and with high intensity grade pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with their resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment). Overhead Informatory road signage	40.00	sqm	5879.90	235196	INR Two Lakh Thirty Five Thousand One Hundred & Ninety Six Only
36	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore	25.00	each	379.20	9480	INR Nine Thousand Four Hundred & Eighty Only
37	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS-15622, of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. complete. Size of Tile 600x600 mm	30.00	sqm	1553.45	46604	INR Forty Six Thousand Six Hundred & Four Only
38	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, benching, retiling & testing of joints complete as per direction of Engineer in Charge. External work : 15 mm nominal; dia pipes	20.00	metre	244.70	4894	INR Four Thousand Eight Hundred & Ninety Four Only

39	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 20 mm nominal dia Pipes	20.00	metre	274.30	5486	INR Five Thousand Four Hundred & Eighty Six Only
40	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 40 mm dia	5.00	each	119.55	598	INR Five Hundred & Ninety Eight Only
41	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	2.00	each	6515.55	13031	INR Thirteen Thousand & Thirty One Only
42	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White	2.00	each	1190.65	2381	INR Two Thousand Three Hundred & Eighty One Only
43	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames etc. including 62x19 mm beading of second class teak wood and priming coat with approved steel primer all complete.	50.00	sqm	1641.15	82058	INR Eighty Two Thousand & Fifty Eight Only
44	25 mm thick PVC flush door shutters made out of a one piece Multi chamber extruded PVC section of the size of 762 mm X mm or less as per requirement with an average wall thickness of 1 mm (x 0.3 mm). PVC foam end cap of size 23x10 mm are provided on both vertical edges to ensure the overall thickness of 25 mm. M.S. tube having dimensions 19 mm x 19 mm and 1.0 mm (x 0.1 mm) is inserted along the hinge side of the door. Core of the door shutter should be with High density Polyurethane foam. The Top & Bottom edges of the shutter are covered with an end-cap of the size 25 mm X 11 mm. Door shutter shall be reinforced with special polymeric reinforcements as per manufacturer's specification and direction of Engineer-in-charge to take up necessary hardware and fixtures. Stickers indicating the locations of hardware will be pasted at appropriate places	7.00	sqm	3068.85	21482	INR Twenty One Thousand Four Hundred & Eighty Two Only
Add GST correction factor (0.973)						
Total in Figures						
Quoted Rate in Figures					5199334.00	INR Fifty One Lakh Ninety Nine Thousand Three Hundred & Thirty Four Only
Quoted Rate in Words					3436239.84	INR Thirty Four Lakh Thirty Six Thousand Two Hundred & Thirty Nine and Paise Eighty Four Only
					Less (-)	33.91%
					INR Thirty Four Lakh Thirty Six Thousand Two Hundred & Thirty Nine and Paise Eighty Four Only	


 Executive Engineer
 HCD-10/00A

judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought in 7 days after the date of issue of this letter, failing which the amount shall be withdrawn.