



DELHI DEVELOPMENT AUTHORITY
OFFICE OF THE EXECUTIVE ENGINEER
COMMONWEALTH GAMES DIVISION NO.1
SCHOOL BLOCK, SHAKARPUR, DELHI – 110092
E-mail: eecgd1_dda@yahoo.com
Ph. No. 011-22481602(Off.)

No. F.5 (359)2022-2023/EE/CGD-1/A/DDA/ 1835

Date: 13/3/24

To,

Sh. Mohd. Samee Siddiqui
Regd. Office:
879, Street No 30/5, Indra Chowk,
Jafrabad
Delhi – 110053
Correspondence Address:
B-86, Kh. No. 120, Chauhan Banger
Delhi 110053

Name of work: Maintenance of Completed Scheme under NA-II at CWG Village Site.
SH: Repair of Rolling Shutters at ESS-1, welded steel grill and road marking at CWGV.
E-tender ID : 2024_DDA_789640_1
NIT No. : 09/EE/CGD.1/DDA/2023-2024
Estimated cost: Rs.1078467/-
Reference: 1. Letter of Intent No F.5 (359)2023-2024/EE/CGD-1/A/DDA/1714 Dated 29/02/2024
2. Performance Guarantee submitted in shape FDR No. 7575384 dt. 04/03/2024 amounting to Rs.25350/- of IDBI Bank Ltd.

Dear Sir,

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your tendered tender rates as per detail given below: -

1.	Estimated cost	Rs.1078467/- (Rupees Ten lakh seventy eight thousand four hundred sixty seven only).
2.	Quoted and accepted rate	@ (-)53.00% below (Fifty three point zero zero percent below) the estimated cost on DSR- 2021
3.	Quoted tender amount	Rs.506879/- (Rupees Five lakh six thousand eight hundred seventy nine only).
4.	Accepted tender amount	Rs.506879/- (Rupees Five lakh six thousand eight hundred seventy nine only). (As per Annexure enclosed).

You are requested to attend this office along with a non-judicial stamp paper worth Rs.100/- (Rupees one hundred only) to complete formal Agreement within 15 days from the date of issue of this letter.


You are requested to contact Asstt. Engineer-2 of this Division and to start the work at once. Please note that the time allowed for carrying out the work as entered in the tender shall be reckoned 10th day after the date of issue of letter of award to commence the work.

The time allowed for execution of the work will be 60 (Sixty) days only.

Thanking You,


Encl.: Annexure Schedule of quantity.

Yours faithfully,


(Rajeev Kr. Sharma)
Executive Engineer
C.G.D.1/D.D.A.

Copy to: -

1. Chief Engineer/EZ/ DDA.
2. S.E./Eastern Civil Circle-2 /DDA.
3. Director (System), DDA through E-Mail ddatender@dda.gov.in for hosting the award letter on DDA's website www.dda.gov.in
4. Secy. (CRB), DDA.
5. Dy. CAO/CAU/EZ/DDA.
6. All Executive Engineers, Eastern Maintenance Divisions & Commonwealth Games Divisions-3 & 4, DDA.
7. Labour Commissioner, 5, Sham Nath Marg, Delhi-54 for information please.
8. EE (QAC) I, DDA.
9. Income Tax Officer (Contractor Circle), 21st Floor, Civic Centre, Minto Road, New Delhi-110002.
10. Sales Tax Officer (Work Contract Cell), Ward No.4, Bikri Kar Bhawan, ITO, New Delhi.
11. Sr. A.O. (Works)-I/DDA.
12. F.O. to C.E. /East Zone/ D.D.A.
13. Sr. A.O./CAU/EZ/DDA.
14. A.E.-2, CGD.1, D.D.A. along with a copy of Annexure Schedule of Quantity with the following direction: -
 - a) To get relevant register from CB/CGD-1/DDA under the signature of undersigned.
 - b) Test check/record of measurement on all important/hidden items is to be done by AE to the extent of 100%.
15. A.E. (P)/CGD.1/DDA.
16. A.S.O., C.G.D.1, D.D.A.
17. Copy to agreement and all concerned files.


Executive Engineer
C.G.D.-1/D.D.A.


ANNEXURE (SCHEDULE OF QUANTITY)

Name of work: Maintenance of Completed Scheme under NA-II at CWG Village Site.
SH: Repair of Rolling Shutters at ESS-1, welded steel grill and road marking at CWGV.
E-tender ID: 2024_DDA_789640_1 NIT No. : 09/EE/CGD.1/DDA/2023-2024

Item No.	Item Description	Quantity	Units	Rate		AMOUNT	
				Rs.	P	Rs.	P
1.00	Repair and maintenance including oiling, greasing, cleaning, replacement of damaged wire spring etc. all complete by opening and refixing in smooth opera national position or Existing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and joined shaft with bracket, side guide and arrangement for inside and outside locking with push and pull operation complete necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS : 4454-p 1 and M.S top cover of required thickness for rolling shutters. (a) 80x1.25mm M.S laths with 1.25mm thick top cover.	129.80	Sqm	457.30		59358.00	
2.00	Replacement of damaged ball bearing for rolling shutters.	8.00	Each	1372.50		10980.00	
3.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared.	1597.00	Sqm.	14.50		23157.00	
4.00	Replacing of damaged old rectangular shape 500x500 mm precast R.C.C. main hole cover without frame. M.D.10	15.00	Each	887.55		13313.00	
5.00	Lettering with black Japan paint of approved brand and manufacture.	5510.00	Per letter Per cm Height	5.05		27826.00	
6.00	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	27.60	Sqm	2038.55		56264.00	

7.00	Providing and applying 2.5mm thick road marking strips (retro-reflective) of specified shade / colour using hot thermoplastic material by fully/semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	533.00	Sqm.	623.80	332485.00
8.00	Providing and fixing Glow studs of size 100x20mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acryloretite) or HIP (High impact polystyrene) or ABS having electronically welded micro-prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro-reflective surface shall be 35(+/-5) degrees to base. The reflective panels on both sides with at least 12 cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM I: 809 as recommended in BS: 873 part 4: 1973. The studs shall be fixed to the road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete and as per direction of Engineer-in-charge.	200.00	Each	175.50	35100.00
9.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: (a) One or more coats on old work.	2130.00	Sqm.	86.55	184352.00
10.00	Finishing walls with water proofing cement paint of required shade: (a) Old work (one or more coats applied @ 2.20 kg/10sqm) complete.	405.00	Sqm.	63.25	25616.00
11.00	Finishing walls with water proofing cement paint of required shade: (a) New work (Two or more coats applied @ 3.84 kg/10 sqm) .	157.00	Sqm	97.60	15323.00
12.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	281.00	Kg.	111.95	31458.00
13.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	82.00	Sqm.	131.45	10779.00
14.00	Providing and fixing in position precast RCC horizontal grating with frame complete of size 500x450 as per standard design.	10.00	nos.	1030.20	10302.00

15.00	Welding by gas or electric plant including transportation plant at site etc complete.	575.00	Cm	3.40	1955.00
16.00	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.00	Cum.	219.35	219.00
17.00	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	157.00	Sqm	540.35	84835.00
18.00	Providing and fixing ABS material plastic breaker of size 500x400x75 mm in black and yellow colour finished to the road surface using the adhesive conforming to IS as per procedure recommended by the manufacturer complete and as per direction of Engineer-in-charge.	30.00	Sqm	3031.40	90942.00
19.00	Add GST factor 0.0633 on amount of item No. 1 to 18.	1014264.00	GST factor	0.0633	64203.00
Total in Figures					1078467.00
Quoted Rate in Figures			Less (-)	(-)53.00% below	(-)571588.00
Quoted and accepted amount in Figures					506879.00
Quoted and accepted amount in Words					Rupees Five Lakh Six Thousand Eight Hundred & Seventy Nine only


 (Rajeev Kr. Sharma)
 Executive Engineer
 C.G.D.1/D.D.A.