



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092
E-mail: eehcdx@gmail.com

No. F.1 (06)2026-2027/ HCD-10/A/DDA/ 161

Date: 18-8-26

To,

M/s Gaurav Construction Co.
164/1 Village Saboli
Railway Road Delhi-110093
M.No.: 9811574567, 9811848282
Email:- sharmapankaj1234567890.ps@gmail.com

Name of work : M/o Completed Scheme under NA-II (Hort Zone)
SH Providing and laying CPVC pipeline and hydrants in ASITA East DDA
Land
E-tender ID : 2026_DDA_918472_1
NIT No. : 05/EE/HCD-10/DDA/2026-27
Estimated cost: Rs 27,23,165/-
Earnest money: Rs 54,463/-
Time Allow : 45 Days
PG : PG submitted vide FDR No. 17913673 dt. 10.08.2026 for Rs. 746692/-

Dear Sir(s),

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rate subject to following terms & condition:-

1.	Estimated Cost	Rs. 27,23,165/- (Rupees Twenty Seven Lakh Twenty Three Thousand One Hundred Sixty Five Only).
2.	Quoted and accepted rate (Contractor's Enhancement)	@(-) 42.42 % below on the Estimated Cost.
3.	Quoted Tender Amount	Rs. 15,67,998.41 (Rupees Fifteen Lakh Sixty Seven Thousand Nine Hundred Ninety Eight and Paise Four One Only)
4.	Accepted Tender Amount	Rs. 15,67,998.41 (Rupees Fifteen Lakh Sixty Seven Thousand Nine Hundred Ninety Eight and Paise Four One Only)


Time allowed for carrying out the work shall **45 Days** only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work. You are requested to contact A.E.-VII /HCD-10/DDA of this division and start the work immediately.

Thanking you,

Yours faithfully


(Sandeep Kushwaha)
Executive Engineer
HCD-10/D.D.A.

Copy to :-

1. C.E. (Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. A.E.-VII /HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. DDA Website.
19. Agreement copy.

Executive Engineer
HCD-10/D.D.A.

Percentage Boq

Tender Inviting Authority: Delhi Development Authority

Name of Work: Mto completed scheme under NA-II Hort. Zone.

SH:- Providing and laying CPVC pipeline and hydrants in ASITA east DDA land.

NIT No: 05/EE/HCD-10/DDA/2026-27

Name of the Bidder/ Bidding Firm /	GAURAV CONSTRUCTION CO.
PRICE SCHEDULE	

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer-in-charge. External work - 50 mm nominal dia Pipes	3	4 metre	5 794.25	6 263537.39	7 INR Twenty Six Lakh Thirty Five Thousand Three Hundred & Thirty Seven Only
2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work - 25mm nominal dia pipes	52.50	metre	355.40	18658.50	INR Eighteen Thousand Six Hundred & Fifty Nine Only
3	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement :4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (inside) with hinged cover fixed in reinforced cement concrete slab 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size), including necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design : With common burnt clay F.P.S (non modular) bricks of class designation 7.5	70.00	each	1992.60	139482.00	INR One Lakh Thirty Nine Thousand Four Hundred & Eighty Two Only

4	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	15.00	mtr	39.35	590.25	INR Five Hundred & Ninety Only
5	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	5.65	sqm	131.75	744.39	INR Seven Hundred & Forty Four Only
6	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost)	5.65	sqm	402.95	2276.67	INR Two Thousand Two Hundred & Seventy Seven Only
7	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old Kerb stones shall be supplied by the department free of cost)	15.00	mtr	109.45	1641.75	INR One Thousand Six Hundred & Forty Two Only
Correction factor @0.973						
Total in Fig	Note:- The excavation work for laying CPVC Pipelines shall be carried out exclusively through manual labour. Deployment of excavators or any other mechanical means for trench excavation shall not be permitted.				2723165.00	INR Twenty Seven Lakh Twenty Three Thousand One Hundred & Sixty Five Only
Quoted Rate in Figures		Less (-)	42.42%		1567998.41	INR Fifteen Lakh Sixty Seven Thousand Nine Hundred & Ninety Eight and Paise Forty One Only
Quoted Rate in Words		INR Fifteen Lakh Sixty Seven Thousand Nine Hundred & Ninety Eight and Paise Forty One Only				


 Executive Engineer
 HCD-18/MDA