



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI-110092
E-mail: eehcdx@gmail.com

No. F.1 (03)2026-2027/EE/HCD-10/A/DDA/106

Date: 19-6-26

To,

✓ M/s N.K. Constructions
D-368, Ganesh Nagar
Padav Nagar Complex
Delhi – 110092
M. No. 9911656527

Name of work : M/o Various Biodiversity Parks
SH : Miscellaneous civil works for Eco-Restoration of Kamla Nehru Ridge
E-tender ID : 2026_DDA_910003_1
NIT No. : 02/EE/HCD-10/DDA/2026-27
Estimated cost: Rs 26,77,023/-
Earnest money: Rs 53,540/-
Time Allow : 60 Day
Ref.: P.G. submitted in shape of FDR A/c No 45283295064 dated
16.06.2026 amounting to Rs 2,90,725/-

Dear Sir(s),

Your percentage rate tender for the above-mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rate subject to following terms & condition: -

1.	Estimated Cost	Rs. 26,77,023/- (Rupees Twenty-Six Lakh Seventy-Seven Thousand Twenty-Three Only).
2.	Quoted and Accepted Amount	@ (-) 25.86% below (Twenty-Five point Eighty Six percent below) on estimated cost.
3.	Quoted tender amount	Rs. 19,84,744.85 (Rupees Nineteen Lakh Eighty Four Thousand Seven Hundred Forty Four and Paise Eighty Five Only)
4.	Accepted Tender Amount	Rs. 19,84,744.85 (Rupees Nineteen Lakh Eighty Four Thousand Seven Hundred Forty Four and Paise Eighty Five Only)


Time allowed for carrying out the work shall **60 Days** only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work. You are requested to contact A.E-III&V/HCD-10/DDA of this division and start the work immediately.

Thanking you,

Yours faithfully


(Sandeep Kushwaha)
Executive Engineer
HCD-10/D.D.A.

Copy to:-

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE-III&V/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. DDA Website.
19. Agreement copy.

Executive Engineer
HCD-10/D.D.A.

Print Help
g Authority: Delhi Development Authority
k: Mo various Biodiversity Park
aneous civil works for Eco-Restor
/EE/HCD-10/DDA/2026-27
N K CONSTRUCTIONS
der/ g
his BOQ template mu
NUMBER #
Sl. No.
1
1

Inviting Authority: Delhi Development Authority

Work: M/o various Biodiversity Park.

miscellaneous civil works for Eco-Restoration of Kamla Nehru Ridge.

DO: 02/EE/HCD-10/DDA/2026-27

Name of Bidder/
Firm /

N K CONSTRUCTIONS


PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / in manual means in foundation trenches or drains (not exceeding 1.5 m width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a)All kinds of soil.	8.00	cum	260.30	2082	INR Two Thousand & Eighty Two Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size derived a natural sources)	3.00	cum	6518.60	19556	INR Nineteen Thousand Five Hundred & Fifty Six Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :a) 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size derived a natural sources)	10.00	cum	7878.50	78785	INR Seventy Eight Thousand Seven Hundred & Eighty Five Only
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	32.86	cum	7132.25	234366	INR Two Lakh Thirty Four Thousand Three Hundred & Sixty Six Only
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	8.00	cum	196.00	1568	INR One Thousand Five Hundred & Sixty Eight Only
6	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	15.00	cum	2123.75	31856	INR Thirty One Thousand Eight Hundred & Fifty Six Only

7	Cement Plaster (In fine sand) 12 mm cement plaster of mix : Cement mortar 1:6 (1 cement : 6 fine sand)	14.90	Sqm	333.35	4967	INR Four Thousand Nine Hundred & Seven Only
8	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm)	14.90	sqm	116.90	1742	INR One Thousand Seven Hundred & Forty Two Only
9	Providing and laying matt finished vitrified tile of size 300x300x9.8 mm having with water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20 mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge	40.00	sqm	1455.65	58226	INR Fifty Eight Thousand Two Hundred & Twenty Six Only
10	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 20 mm dia nominal bore	300.00	metre	368.60	110580	INR One Lakh Ten Thousand Five Hundred & Eighty Only
11	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 40 mm dia nominal bore	550.00	metre	617.05	339378	INR Three Lakh Thirty Nine Thousand Three Hundred & Seventy Eight Only
12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 50 mm dia nominal bore	1000.00	metre	762.15	762150	INR Seven Lakh Sixty Two Thousand One Hundred & Fifty Only
13	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	700.00	kg	117.35	82145	INR Eighty Two Thousand One Hundred & Forty Five Only
14	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	539.87	kg	194.40	104951	INR One Lakh Four Thousand Nine Hundred & Fifty One Only
15	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	50.00	sqm	226.25	11313	INR Eleven Thousand Three Hundred & Thirteen Only

	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, total excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	75.00	sqm	738.65	55399	INR Fifty Five Thousand Three Hundred & Ninety Nine Only
17	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	45000.00	per litre	11.00	495000	INR Four Lakh Ninety Five Thousand Only
18	Providing and fixing prefabricated portable MS Container Site office cabins, manufactured using MS corrugated sheets (Thickness: 1.2 mm – 18 gauge) with inner sides laminated using MDF boards (Thickness: 6 mm). Flooring is done using cement fiber board's (Thickness: 20 mm, Make Everest) then a layer of Vinyl flooring. For insulation expanded polystyrene (Thickness: 25 mm) is used. The container will be duly painted Outside and Inside. The container is water proof, termite & heat resistant; making it comfortable in extreme hot or cold climate at site of size 20'X10' feet having 2 no. door, 4 no. window table, fan, tubelight, switches, 2 no. Ac point etc. all complete as per direction of Engineer-in-Charge.	1.00	Each	354236.50	354237	INR Three Lakh Fifty Four Thousand Two Hundred & Thirty Seven Only
19	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (including equivalent design mix)	2.00	cum	1503.60	3007	INR Three Thousand & Seven Only
	Add correction factor@0.973					
Total in Figures						
Quoted Rate in Figures					2677023.00	INR Twenty Six Lakh Seventy Seven Thousand & Twenty Three Only
Quoted Rate in Words					Less (-) 25.86%	1984744.85
INR Nineteen Lakh Eighty Four Thousand Seven Hundred & Forty Four and Paise Eighty Five Only						


 Executive Engineer
 HCD, INDIA