



OFFICE OF THE EXECUTIVE ENGINEER  
HORTICULTURE CIVIL DIVISION NO.10  
D.D.A., SCHOOL BLOCK, SHAKARPUR,  
DELHI - 110092  
E-mail: eehcdx@gmail.com

Date: 26/5/28

No. F.1 (310)2025-2026/EE/HCD-10/A/DDA | 77

To,

Sh. Rahul Suryavanshi,  
D-368, Ganesh Nagar,  
Pandav Nagar Complex,  
Delhi-110092,  
E-mail: rahulsuryavanshi92@gamil.com

Name of work : M/o Northern Ridge KNR  
SH : Repairing and construction of existing boundary wall along with fencing  
at Kamla Nehru Ridge  
E-tender ID : 2026\_DDA\_900353\_1  
NIT No. : 31/EE/HCD-10/DDA/2025-26 (15/EE(P)/HCC-3/DDA/2025-26)  
Estimated cost: Rs 97,82,955/-  
Ref : P.G. submitted in shape of FDR A/c No 45201546355 dt. 21.05.2026  
amounting to Rs 1947787/-

Dear Sir,

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rates subject to following terms & condition:-

1.	Estimated Cost	Rs. 97,82,955/- (Rupees Ninety Seven Lakh Eighty Two Thousand Nine Hundred Fifty Five Only)
2.	Quoted & Accepted Rate (Contractor's Enhancement)	@(-) 34.91 % below (Thirty Four point Nine One percent) below on estimated cost
3.	Quoted Tender Amount	Rs. 63,67,725.41 (Rupees Sixty Three Lakh Sixty Seven Thousand Seven Hundred Twenty Five and paise Forty One Only).
4.	Accepted Tender Amount	Rs. 63,67,725.41 (Rupees Sixty Three Lakh Sixty Seven Thousand Seven Hundred Twenty Five and paise Forty One Only).


Time allowed for carrying out the work shall 90 Days only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 3 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work. You are requested to contact A.E.-V/HCD-10/DDA of this division and start the work immediately.

Thanking you,

Yours faithfully

  
(Sandeep Kushwaha)  
Executive Engineer  
HCD-10/D.D.A.

**Copy to :-**

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE-V/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. DDA's Website.
19. Agreement copy.

Executive Engineer  
HCD-10/D.D.A.

Percentage BoQ

ender Inviting Authority: Delhi Development Authority  
 Name of Work: M/o Northern Ridge KNR.  
 SH:- Repairing and construction of existing boundary wall along with fencing at Kamla Nehru Ridge.

NIT No: 15/EE(P)/HCC-3/DDDA/2025-26  
 31/EE/HCD-10/DDDA/2025-26

Name of the Bidder/ Bidding Firm / RAHUL SURYAVANSHI

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in P	TOTAL AMOUNT in P	TOTAL AMOUNT In Words	
1	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : In cement mortar	79.00	cum	2458.95	194257	INR One Lakh Nirety Four Thousand Two Hundred & Fity Seven Only	7
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	9.00	cum	2434.25	21908	INR Twenty One Thousand Nine Hundred & Eight Only	
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 2.8.1 All kinds of soil.	104.00	cum	260.30	27071	INR Twenty Seven Thousand & Seventy One Only	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-II)) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources).	7.00	cum	6518.60	45630	INR Forty Five Thousand Six Hundred & Thirty Only	

5	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : 1. Cement mortar 1:6 (1 cement : 6 coarse sand), Stone received from demolition to be issued free of cost.	47.00	cum	5035.00	236645	INR Two Lakh Thirty Six Thousand Six Hundred & Forty Five Only
6	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : 1. Cement mortar 1:6 (1 cement : 6 coarse sand).	32.00	cum	7311.25	233960	INR Two Lakh Thirty Three Thousand Nine Hundred & Sixty Only
7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	4.00	cum	2060.20	8241	INR Eight Thousand Two Hundred & Forty One Only
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	202.00	cum	7132.25	1440715	INR Fourteen Lakh Forty Thousand Seven Hundred & Fifteen Only
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: a) Cement mortar 1:6 (1 cement : 6 coarse sand)	78.00	cum	9105.95	710264	INR Seven Lakh Ten Thousand Two Hundred & Sixty Four Only
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-II)) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	46.00	cum	8340.85	383679	INR Three Lakh Eighty Three Thousand Six Hundred & Seventy Nine Only
11	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	7728.00	kg	3.85	29753	INR Twenty Nine Thousand Seven Hundred & Fifty Three Only
12	Providing and fixing hard drawn steel wire fabric of size 75 x25 mm mesh or other suitable size wire mesh to be fixed & firmly anchored to the concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineer-in-charge.	1918.00	sqm	902.55	1731091	INR Seventeen Lakh Thirty One Thousand & Ninety One Only
13	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	12058.00	kg	133.70	1612155	INR Sixteen Lakh Twelve Thousand One Hundred & Fifty Five Only
14	Refixing of built-up section in proper line & level as per direction of Engineer-in-charge.	5293.00	kg	11.40	60340	INR Sixty Thousand Three Hundred & Forty Only

Painting of required under coat of shade with ordin  
Painting with synthetic of required colour to give  
Centering

16

17

16	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	1048.00	sqm	226.25	237110	INR Two Lakh Thirty Seven Thousand One Hundred & Ten Only
17	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :a)One or more coats on old work	438.00	sqm	102.80	45026	INR Forty Five Thousand & Twenty Six Only
18	Centering and shuttering including strutting, propping etc. and removal of form work for :a) Foundations, footings, bases for columns	248.00	sqm	392.15	97253	INR Ninety Seven Thousand Two Hundred & Fifty Three Only
19	Removing mortar from and cleaning stones and concrete articles (net quantity of stacks of cleaned materials will be measured): In cement mortar	47.00	cum	689.20	32392	INR Thirty Two Thousand Three Hundred & Ninety Two Only
20	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Raised and cut pointing.	879.00	sqm	701.05	616223	INR Six Lakh Sixteen Thousand Two Hundred & Twenty Three Only
21	Extra for random rubble masonry with hard stone curved on plan for a mean radius not exceeding 6 m.	42.00	cum	1046.20	43940	INR Forty Three Thousand Nine Hundred & Forty Only
22	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	73.00	cum	263.95	19268	INR Nineteen Thousand Two Hundred & Sixty Eight Only
23	Precasting and placing in position 150 mm dia Bollards 950 mm high of required shape including providing M.S pipe sleeve 50 mm dia 300 mm long in the Bollards and M.S pipe 40 mm dia and 700 mm long with 150X150X6 mm M.S plate welded at bottom and embedded 150mm in cement concrete 1:3:6 (1 cement : 3 coarse sand (Zone-III) : 6 graded stone aggregate 20 mm nominal size) , including necessary excavation of size 300X300X350 mm deep for the same in bitumen/concrete pavement at specified spacing.	100.00	Each	1131.65	113165	INR One Lakh Thirteen Thousand One Hundred & Sixty Five Only
24	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from ] natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	8.00	cum	7294.70	58358	INR Fifty Eight Thousand Three Hundred & Fifty Eight Only
25	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand)	1012.00	sqm	333.35	337350	INR Three Lakh Thirty Seven Thousand Three Hundred & Fifty Only
26	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	1012.00	sqm	383.00	387596	INR Three Lakh Eighty Seven Thousand Five Hundred & Ninety Six Only

26	Finishing walls with water proofing cement paint of required shade : 1. New work (Two or more coats applied @ 3.84 kg/10 sqm)	2024.00	sqm	116.90	236606	INR Two Lakh Thirty Six Thousand Six Hundred & Six Only
27	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	14986.00	sqm	75.80	1135939	INR Eleven Lakh Thirty Five Thousand Nine Hundred & Thirty Nine Only
28	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineer-in-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.) a) Slurr mixed Acrylic Polymer of approved make @ 2% of weight of cement used) modified Cement slurry made with non shrink compound in concrete/RCC work	92.00	kg	119.30	10976	INR Ten Thousand Nine Hundred & Seventy Six Only
29	Disposal of dismantled old fencing as per the direction of Engineer-in-Charge/Recovery on the account of scrap/dismantle steel etc shall be measured on actual weight; basis of the dismantle steel angles and wire mesh will be recovered from the bill @ Rs. 35 per kg from the agency). Nothing will be paid on a/c of dismantling and carriage etc.	1546.00	kg	-33.95	-52487	INR Minus Fifty Two Thousand Four Hundred & Eighty Seven Only
Total in Figures		Reduction factor (0.973)				
Quoted Rate in Figures		9782955.00				INR Ninety Seven Lakh Eighty Two Thousand Nine Hundred & Fifty Five Only
Quoted Rate in Words		INR Sixty Three Lakh Sixty Seven Thousand Seven Hundred & Twenty Five and Paise For One Only	Less (-)	34.91%	6367725.41	INR Sixty Three Lakh Sixty Seven Thousand Seven Hundred & Twenty Five and Paise For One Only

  
 Executive Engineer  
 HCD-10/IDDA

