



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092
E-mail: eehcdx@gmail.com

No. F.1 (291)2025-2026/EE/HCD-10/A/DDA / 399

Date: 30/9/25

To,

Sh. Mohit Kumar Pundhir
K-19/1560 Ground Floor,
Sangam Vihar, New Delhi-110080

Name of work: M/o completed scheme under Nazul A/c-II/Hort. Zone.
SH : Restoration and Renovation of Yamuna Signage Boards
between Wazirabad Barrage to NH-24 (Eastern & Western
bank).
E-tender ID : 2025_DDA_869524_1
Estimated cost: Rs. 2348068/-
Ref. : P.G. submitted in shape FDR A/c No 028623030005138 dt.
06.09.2025 amounting to Rs.70000/-

Dear Sir,

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rate subject to following terms & condition:-

1.	Estimated Cost	Rs. 2348068/- (Rupees Twenty Three Lakh Forty Eight Thousand and Sixty Eight only).
2.	Quoted and accepted rate (Contractor's Enhancement)	@(-)41.97% below on the Estimated Cost.
3.	Quoted Tender Amount	Rs 1362583.86 (Rupees Thirteen Lakh Sixty Two Thousand Five Hundred Eighty Three and paisa Eighty Six only)
4.	Accepted Tender Amount	Rs 1362583.86 (Rupees Thirteen Lakh Sixty Two Thousand Five Hundred Eighty Three and paisa Eighty Six only)

Time allowed for carrying out the work shall **60 Days** only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work. You are requested to contact A.E.-I/HCD-10/DDA of this division and start the work immediately.


Thanking you,

Yours faithfully

(Sandeep Kushwaha)
Executive Engineer
HCD-10/D.D.A.

Copy to:-

1. C.E. (Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. A.E.-I/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. DDA Website.
19. Agreement copy.


Executive Engineer
HCD-10/D.D.A

Inviting Authority: Delhi Development Authority

Name of Work: Mo completed scheme under Nazul A/C-II/Hort. Zone.

SH:- Restoration and Renovation of Yamuna Signage Boards between Wazirabad Barrage to NH-24 (Eastern bank & western bank).

NT No: 13/EEHCD-10/DDA/2025-26

Name of the Bidder/ Bidding Firm/

MOHIT KUMAR PUNDHIR

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	1.44	Cum	260.30	375	INR Three Hundred & Seventy Five Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a)1:5:10 (1 cement : 5 coarse sand (zone-II)) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	0.144	Cum	6518.60	939	INR Nine Hundred & Thirty Nine Only
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : a)1:2:4 (1 cement : 2 coarse sand (zone-II)) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.20	Cum	8583.40	10300	INR Ten Thousand Three Hundred Only
4	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	96.00	Kg.	97.20	9331	INR Nine Thousand Three Hundred & Thirty One Only
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	226.08	Kg.	123.60	27943	INR Twenty Seven Thousand Nine Hundred & Forty Three Only

	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge. (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	722.68	Kg.	772.40	558198	INR Five Lakh Fifty Eight Thousand One Hundred & Ninety Eight Only
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Thermo-Mechanically Treated bars of grade Fe-500D or more.	72.00	Kg.	107.85	7765	INR Seven Thousand Seven Hundred & Sixty Five Only
8	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	4.80	Sqm	392.15	1882	INR One Thousand Eight Hundred & Eighty Two Only
9	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	300.00	Kg	2.30	690	INR Six Hundred & Ninety Only
10	Providing crane of 20 tonne capacity at site on Hire charge Basis including driver and fuel etc. all complete as per direction of Engineer-in-charge.	14.00	day	10866.55	152132	INR One Lakh Fifty Two Thousand One Hundred & Thirty Two Only
11	Manufacturing, supplying and fixing informatory signage boards made up of 4mm thick ACP sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type -III of ASTM-D-4956-01 as approved by Engineer-in-charge. letters borders etc. as per IRC:67-2001 in silver white with blue/other colour back ground with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloy, rivets or bolts & nuts @ 300mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures. The rate includes the cost of rounding off the corners, fixing and erecting the same in position all complete as per drawings, specification and direction of the Engineer-in-charge. (Structural frame work including S.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment).	312.90	Sqm	4325.00	1353293	INR Thirteen Lakh Fifty Three Thousand Two Hundred & Ninety Three Only
12	Manufacturing, supplying and fixing retro reflective 3D letters/logo made of 1mm thick stainless steel sheet, face to be fully covered with high conforming to type -IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per drawings and directions of Engineer-in-charge, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class- 2 of ASTM-D-4956-01 and fixing the same with main frame through welding and back support frame of S.S box section of size 25x25x2 mm along with theft resistant measures, complete as per drawing, specification and direction of Engineer-in-charge. (Rectangular/Circular area of words & logo only shall be measured or payment).	35.00	Sqm	8488.00	297080	INR Two Lakh Ninety Seven Thousand & Eighty Only

13	Recovery on the account of the scrap /dismantled steel etc.shall be measured on actual weight basis on the dismantled stainless steel pipes and tubes will be recovered from the bill @Rs 120/kg from the agency.(nothing will be paid on account of carriage etc.)	1.00	each	-18000.00	-18000	INR Minus Eighteen Thousand Only
14	Recovery on the account of the dismantled ACP Sheet etc.shall be measured on actual weight basis on the dismantled ACP Sheet will be recovered from the bill @Rs 32/kg from the agency.(nothing will be paid on account of carriage etc.)	1.00	each	-37190.40	-37190	INR Minus Thirty Seven Thousand One Hundred & Ninety Only
	Correction factor @0.973 on DSR Items 1 to 9 i.e. (617423*0.973)				2348068.00	INR Twenty Three Lakh Forty Eight Thousand & Sixty Eight Only
Total in Figure	Note: Contractor shall follow the relevant NGT, DPCC orders, and or any other govt. authority enforcing environmental and pollution control orders and if any fine/penalty/challan is imposed by any government agency, the cost of the same shall be solely borne by the contractor.					INR Thirteen Lakh Sixty Two Thousand Five Hundred & Eighty Three and Paise Eighty Six Only
Quoted Rate in Figures			Less (-)	41.97%	1362583.86	
Quoted Rate in Words		INR Thirteen Lakh Sixty Two Thousand Five Hundred & Eighty Three and Paise Eighty Six Only				


 Executive Engineer
 HCD-10/EDDA