



दिल्ली विकास प्राधिकरण / Delhi Development Authority
कार्यालय अधिशाषी अभियंता / O/o Executive Engineer
द्वारका रखरखाव खंड-II / Dwarka Maintenance Division -II
केन्द्रीय नर्सरी सेक्टर-5 द्वारका / Central Nursery, Sector -5, Dwarka
नई दिल्ली:- ११००७५ / New Delhi -110075
ईमेल - eedmd2@dda.org.in

No.F(54)(2192)/EE/DMD-II/DDA/2026-27/A | 808

Date- 07.07.26

To
M/s Malik Constructions
H-87, Kunwar Singh Nagar
Near Nilothi More, Nangloi
New Delhi-110041

NIT NO. : 01/EE/DMD-II/DDA/2026-27.

N.O.W : M/o various colonies under Nazul A/c-II, Dwarka Zone.
SH : Dismantling and Recasting of deteriorated storm water drain slab in
Sec-16 & 17 (30m Row) , under jurisdiction of DMD-II , Dwarka Zone.

Your percentage rate tender for the above noted work has been accepted on behalf of Delhi Development Authority at the rates, terms and conditions given below:-

Estimated cost	: Rs. 7,71,14,687/- (Seven Crore Seventy One Lakhs Fourteen Thousand Six Hundred Eight Seven Only).
Tendered Amount	: Rs.5,01,32,258.02/- (Five Crore One Lakh Thirty Two Thousand Two Hundred and Fifty Eight Only)
Time allowed	: 180 Days
Accepted % age	: (-) 34.99 % below the estimated cost

You are requested to attend this office with a non- judicial stamp paper worth Rs. 100/- to sign the formal agreement within **10 (Ten) days** from the date of issue of this letter failing which the acceptance of work in your favor is likely to be withdrawn and entire amount of performance guarantee deposited by you for this work shall be forfeited to the DDA.

You are also requested to contact AE-III /DMD-II of this division and start the work at once. It may please be noted that the time allowed to carry out the work as entered in the tender document shall be reckoned from **10th day** after the date of issue of acceptance letter or handing over of site whichever is later to commence the work. You are also requested to obtain the project code within five days from the date of execution of agreement.

P. S. Chandra
07.07.26
EXECUTIVE ENGINEER
DMD-II/DDA

Jeel
07.7.26

Copy to:

1. Chief Engineer (DWK), DDA.
2. Chief Engineer (QAC), Vikas Sadan, DDA
3. S.E./DCC-1, DDA
4. The Income Tax Officer (Contractors' Cell), ITO, New Delhi.
5. Dy. Director (System) DDA with the request to e-mail the same in the website of DDA-ddatender@dda.org.in.
6. Labour Commissioner, 15, Rajpur Road, Delhi.
7. Secretary, CRB, DDA, Vikas Minar, New Delhi.
8. All Ex. Engineers, Dwarka Zone, DDA.
9. A.O(Works)-II, DDA.
10. AO(CAU)/Dwarka, DDA.
11. All AEs, H.C, AAO/DMD-II.
12. AE-III /DMD-II, DDA, along with Schedule of Quantities & Rates.
13. Agreement copy.
14. Work File.

Rdhe
07.07.26
EXECUTIVE ENGINEER
DMD-II/DDA

ghe
07.7.26

Validate Print Help

Percentage BoQ

Tender Inviting Authority: DELHI DEVELOPMENT AUTHORITY

Name of Work : - M/o Various colonies under Nazul Account-II, Dwarka Zone.


Sub-Head: Dismantling & Re-casting of deteriorated storm water drain slab in Sec-16 & 17 (30 m RoW), under jurisdiction of DMD-II, Dwarka Zone.

Contract No: 01/EE/DMD-II/DOA/2026-27

Name of the Bidder/ Bidding Firm / Company :		M/S MALIK CONSTRUCTION.				
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Rate in Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge	7335.00	Sqm.	131.75	966386.00	INR Nine Lakh Sixty Six Thousand Three Hundred & Eighty Six Only
2	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks and coarse sand shall be supplied by the department free of cost).	5134.00	Sqm.	299.80	1539173.00	INR Fifteen Lakh Thirty Nine Thousand One Hundred & Seventy Three Only
3	Providing and laying 60 mm thick factory made cement concrete paver block of approved shape and colour of M-30 grade made of C&D waste by block making machine with vibratory compaction laid in required pattern and including over 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. Note: Payment shall be made only after submission of C&D waste paver block vouchers.	4052.00	Sqm.	829.75	3362147.00	INR Thirty Three Lakh Sixty Two Thousand One Hundred & Forty Seven Only
4	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	6439.00	Sqm.	113.35	729861.00	INR Seven Lakh Twenty Nine Thousand Eight Hundred & Sixty One Only
5	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	1133.00	Cum.	177.50	201108.00	INR Two Lakh One Thousand One Hundred & Eight Only
6	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge	1645.00	Cum	3551.25	5841806.00	INR Fifty Eight Lakh Forty One Thousand Eight Hundred & Six Only
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:4 (1 cement : 4 coarse sand)	208.00	Cum	7370.65	1533095.00	INR Fifteen Lakh Thirty Three Thousand & Ninety Five Only
8	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	902.00	Sqm.	357.35	322330.00	INR Three Lakh Twenty Two Thousand Three Hundred & Thirty Only
9	6 mm cement plaster 1:3 (1 cement : 3 fine sand) finished with a floating coat of neat cement and thick coat of Lime wash on top of walls when dry for bearing of R.C.C. slabs and beams.	2979.00	Sqm.	396.65	1181620.00	INR Eleven Lakh Eighty One Thousand Six Hundred & Twenty Only
10	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	8287.00	Sqm.	927.25	7684121.00	INR Seventy Six Lakh Eighty Four Thousand One Hundred & Twenty One Only

11	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls above or Equal 20 cm wide	1169.00	Sqm.	879.05	1027609.00	INR Ten Lakh Twenty Seven Thousand Six Hundred & Nine Only
12	Centering and shuttering including strutting, propping etc. and removal of form for Under 20 cm wide	12467.00	Metre	208.55	2599993.00	INR Twenty Five Lakh Ninety Nine Thousand Nine Hundred & Ninety Three Only
13	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge, for the following grades of concrete.: Note: Minimum cement content considered in this item is @ 350 kg/cum extra cement used than specified minimum cement content is not payable, whereas recovery shall be affected for less cement used than specified minimum cement content. All works upto plinth level. Concrete of M30 grade with minimum cement content of 350 kg /cum.	1779.00	Cum	9655.70	17177490.00	INR One Crore Seventy One Lakh Seventy Seven Thousand Four Hundred & Ninety Only
14	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	177900.00	Kg.	107.85	19186515.00	INR One Crore Ninety One Lakh Eighty Six Thousand Five Hundred & Fifteen Only
15	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level - 1:5:10 (1 Cement : 5 manufactured sand derived from Recycled Concrete Aggregate (RCA) : 10 graded stone aggregate 40 mm nominal size Recycled Aggregate (RA))	138.00	Cum.	4911.85	677835.00	INR Six Lakh Seventy Seven Thousand Eight Hundred & Thirty Five Only
16	Painting with synthetic enamel paint of approved brand and manufacture of required color to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	220.00	Sqm.	226.25	49775.00	INR Forty Nine Thousand Seven Hundred & Seventy Five Only
17	Providing and placing in position 100 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways, neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick, 100 mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc i/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge. Note: The cover shall be engraved with project code, name of division/DDA, grade of concrete, make and year of manufacture etc.	493.00	Sqm.	3081.95	1519401.00	INR Fifteen Lakh Nineteen Thousand Four Hundred & One Only
18	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level - 1:2:4 (1 cement : 2 coarse sand (zone-III) including manufactured sand derived from recycled concrete aggregate (RCA) upto 25% : 4 graded stone aggregate 20 mm nominal size including recycled concrete aggregate (RCA) upto 25%	2.00	Cum	7654.85	15310.00	INR Fifteen Thousand Three Hundred & Ten Only
19	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 250 mm dia. R.C.C. pipe	168.00	Metre	899.80	151166.00	INR One Lakh Fifty One Thousand One Hundred & Sixty Six Only
20	Cleaning & Desilting of peripheral/internal SW drain of any width & depth, including taking out dry/wet/semi wet sludge, silt and malba rubbish i/c any dead animal etc. and disposal of the excavated material for all lead & all lift/depth at approved Municipal dumping ground or as per direction of Engineer-in-Charge. Payment shall be made as per plan area of executed drain only. (Before & after drain cleaning photographs has to be submitted by agency)	9275.00	Sqm.	90.50	839388.00	INR Eight Lakh Thirty Nine Thousand Three Hundred & Eighty Eight Only
21	Deduct for taken away the unserviceable steel bars (Scraps) received from dismantling of RCC works as per direction of Engineer-in-charge.	32900.00	Kg.	42.25	-1390025.00	INR Minus Thirteen Lakh Ninety Thousand & Twenty Five Only
22	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Ordinary cement without any pigment	10005.00	Sqm.	1056.35	10568782.00	INR One Crore Five Lakh Sixty Eight Thousand Seven Hundred & Eighty Two Only
23	Providing and laying tactile tile (for vision impaired persons as per standards) of yellow colour having size 300x300x25 mm in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile, including rubbing and cleaning etc. complete on 20mm thick base of cement mortar 1:4(1 cement : 4 coarse sand) as per direction of Engineer-in-charge.	1897.00	Sqm.	1123.75	2131754.00	INR Twenty One Lakh Thirty One Thousand Seven Hundred & Fifty Four Only
24	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	4120.00	Sqm.	102.80	423536.00	INR Four Lakh Twenty Three Thousand Five Hundred & Thirty Six Only

25	Providing and Fixing Cylindrical Bollard 200mm (Top Dia) x 200 mm (Bottom Dia) x 950 mm height manufactured by using M-30 grade of concrete, reinforced (5 nos longitudinal, 5 nos ring of 8 mm dia TOR steel) using vibro compaction process including necessary excavation and cement concrete as per direction of Engineer-in-charge.	125.00	Each	1180.80	148781.00	INR One Lakh Forty Eight Thousand Seven Hundred & Eighty One Only
26	Disposal of Excavated Earth/ building rubbish /malba / similar unserviceable, dismantled or waste materials by mechanical means i/c loading, transporting, unloading to C&D waste plant at Burari/shastri Park/Bakkarwala or any other approved municipal dumping ground or as approved by Engineer-in-charge beyond 50 m initial lead, for all leads including all lifts involved. Charges borne by agency on account of disposal at C&D waste plant shall be reimbursed by the department on actual basis after the submission of receipt of the municipal plant by the contractor etc. all complete as per direction of Engineer-in-charge.	3168.00	Cum.	263.95	836194.00	INR Eight Lakh Thirty Six Thousand One Hundred & Ninety Four Only
Total after GST Correction Factor @ 0.973= 77183372.00						
Add -0.09% Cost Index except Item No. 21, 23 & 25						
Total in Figures					-68685.00	INR Minus Sixty Eight Thousand Six Hundred & Eighty Five Only
Quoted Rate in Figures					77114687.00	INR Seven Crore Seventy One Lakh Fourteen Thousand Six Hundred & Eighty Seven Only
Quoted Rate in Words			Less (-)	34.99%	50132258.02	INR Five Crore One Lakh Thirty Two Thousand Two Hundred & Fifty Eight and Paise Two Only
		INR Five Crore One Lakh Thirty Two Thousand Two Hundred & Fifty Eight and Paise Two Only				


07-07-26
अधिशाली अभियंता
Executive Engineer
द्वारखण्ड-II/दि.वि.प्रा.
D.M.D.-2 / D.D.A.