



दिल्ली विकास प्राधिकरण / Delhi Development Authority
कार्यालय अधिशाषी अभियंता / O/o Executive Engineer
द्वारका रखरखाव खंड-II / Dwarka Maintenance Division -II
केन्द्रीय नर्सरी सेक्टर-5 द्वारका / Central Nursery, Sector -5, Dwarka
नई दिल्ली :- ११००७५ / New Delhi -110075
ईमेल - cedmd2@dda.org.in

No. F54(2184)/EE/DMD-2/DDA/2025-26/A/ 266

Dated: 11/03/2026

To

Sh. Premlal Singh Yadav
Plot No. - 63, G-Block
Qutub Vihar, Phase-1
Post office-Goyla Dairy, Najafgarh
New Delhi-110071

Name of Work: M/o various colonies under Nazul Account-II, Dwarka Zone
Sub-Head: Cleaning and Desilting of SW Drains of MP Road No.226,221 and
30m ROW Roads of Sector-7 & 10 under the jurisdiction of DMD-
II, Dwarka

Ref: F54(2184)/EE/DMD-II/DDA/2025-26/A/206 Dated: 24.02.2026
P.G. Received on: 28.02.2026 for Rs. 1,28,000/- in the shape of Term Deposit
Advice issued by Union Bank of India

Dear Sir,

Your Percentage rate tender for the above-mentioned work is hereby accepted on
behalf of the Delhi Development Authority at the rates, terms & conditions given below:

Estimated Cost: Rs. 28,56,736/- (Rupees Twenty Eight Lakh Fifty Six
Thousand Seven Hundred Thirty Six Only)

Quoted/tendered: Rs.12,48,679/- (Rupees Twelve Lakh Fourty Eight
Thousand Six Hundred Seventy Nine only)


Accepted Amount: Rs.12,48,679/- (Rupees Twelve Lakh Fourty Eight
Thousand Six Hundred Seventy Nine only)

The percentage to be taken for the purpose of Clause-12 of the agreement shall 56.29%
below on the rates based on DSR- 2023.

You are requested to attend the office along with a non-judicial stamp paper worth
Rs. 100/- (Rupees Hundred Only) to complete the formal agreement within ten days from the
date of issue of this letter.


Please note that time allowed for completion of work as entered in the tender shall be
reckoned from the 10th day from the date of issue of this letter to commence the work. The
time allowed for execution of work is 180 days.

You are requested to contact AE -V of this division and start the work immediately.


EXECUTIVE ENGINEER
DMD-II/DDA


Copy to:

1. Chief Engineer (DWK), DDA.
2. Chief Engineer (QAC), Vikas Sadan, DDA
3. S.E./DCC-1, DDA
4. The Income Tax Officer (Contractors' Cell), ITO, New Delhi.
5. Dy. Director (System) DDA with the request to e-mail the same in the website of DDA-ddatender@dda.org.in.
6. Labour Commissioner, 15, Rajpur Road, Delhi.
7. Secretary, CRB, DDA, Vikas Minar, New Delhi.
8. All Ex. Engineers, Dwarka Zone, DDA.
9. A.O(Works)-II, DDA.
10. AO(CAU)/Dwarka, DDA.
11. All AEs, H.C, AAO/DMD-II.
12. AE-V/DMD-II, DDA, along with Schedule of Quantities & Rates.
13. Agreement copy.
14. Work File.


11/03/2016
EXECUTIVE ENGINEER
DMD-II/DDA
11/03/16

Validate Print Help

Percentage Bids

Tender Inviting Authority: DELHI DEVELOPMENT AUTHORITY

Name of Work : - M/o Various colonies under Nezu Account-II, Dwarka Zone

Sub-Head:- Cleaning and Desludging of SW Drain of MR Road No 226,221 and 30 m ROW Roads of Sector 7 & 10 under the jurisdiction of DMD-II, Dwarka

Contract No: 42EEDMD-II/DMA/2035-26

Name of the Bidder/ Bidding Firm / Company : PREM LAL SINGH YADAV

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	NUMBER #	TEXT #	Quantity	Units	NUMBER Rate In P	NUMBER # TOTAL AMOUNT In P	TEXT # TOTAL AMOUNT In Words
1	Cleaning & Desludging of peripheral and internal covered SW drain of any width & depth, including taking out dry/wet/seam wet sludge, silt and malba rubbish etc. (1/c any dead animal etc.) etc. and disposal of the excavated material for all lead & all lift/depth as approved Municipal dumping ground/low lying area or as per direction of Engineer-in-Charge and opening (dismantling old CC if required) & refilling of drain cover with Cement Concrete 1:2:4 (1 cement : 2 coarse sand derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources), cleaning of bell mouth, removal of blockage and obstructions in smooth flow of drain or under water/ liquid mud including pumping out of water, if required in or under foul condition etc all complete as per direction of Engineer-in-Charge. (Before and after GPS enabled photographs/videos has to be submitted by the agency) NOTE :for payment purpose, measurement of plan area of executed drain surface area will be taken).	2	3	4	5	6	7	
							2377353.00	INR Twenty Three Lakh Seventy Seven Thousand Three Hundred & Fifty Three Only
2	Cleaning of choked drain by Diesel running vehicle mounting hydraulic operated high pressure suction jetting cleaning machine fitted with pump having 4000 litres suction capacity and 6000/litres water jetting tank capacity /1 c skilled operator, supervising engineer etc. for cleaning and desludging of drain line and chamber and dechoking of drain, dechoking and flushing of drain line from one chamber to another by high pressure jetting system of 2200 PSI for drain of depth from 900 mm to 2500 mm. (Before and after GPS enabled photographs/videos has to be submitted by the agency)			913.60	metre	324.25	296235.00	INR Two Lakh Ninety Six Thousand Two Hundred & Thirty Five Only
3	Cleaning of kerb channel of main carriageway and of service lane (wherever available) of any width including removing of all kind of material, malba, rubbish, silt and dust etc. and disposal of the same material for all lead & all lift/depth at Municipal dumping ground/low lying area or as per direction of Engineer-in-Charge and opening and cleaning of bell mouth, removal of blockage, creating obstruction in smooth flow of water etc all complete as per direction of Engineer-in-Charge (Before and after GPS Photographs has to be submitted by agency) NOTE :for payment purpose, length of kerb channel will be measured.			25160.00	metre	3.25	81770.00	INR Eighty One Thousand Seven Hundred & Seventy Only
4	Providing and placing in position 100 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100 mm c/c on both ways, neat cement painting on finished surface, properly excavated on all edges with 16 mm thick, 100 mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc including cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.			23.00	Sqm	3081.95	70885.00	INR Seventy Thousand Eight Hundred & Eighty Five Only

5	Making bell mouth opening/ entrance of size 100x50x50 cm for drainage pipe under footpath, including providing cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) for shape of bell mouth, including plastering providing and fixing precast R.C.C./ S.F.R.C. slab including plastering with cement mortar 1:3 (1 cement : 3 fine sand) of 6 mm thickness on exposed surface of the slab & bell mouth including centring, shuttering & neat cement punning inside the bell mouth etc. all complete, as per direction of Engineer-in-charge.	5.00	each	3050.40		13252.00	INR Fifteen Thousand Two Hundred & Fifty Two Only
6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collar jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : a) 250 mm dia. R.C.C. pipe	10.00	metre	899.80		8998.00	INR Eight Thousand Nine Hundred & Ninety Eight Only
	GST correction factor = 0.873=2773530.00						
	Cost Index @ 3%					83208.00	INR Eighty Three Thousand Two Hundred & Six Only
Terms & Conditions:- 1. As this work is time bound & urgent work so if required more than one team shall be mobilised by the agency in case of urgency/emergency, other than normal working hours within two hours of given instructions by Engineer-in-charge. No extra payment shall be made for this. Failure of which penalty of Rs 5000/- shall be imposed on the agency. 2. In case of any emergency, the agency shall have to deploy the team even in odd hours i.e. night hours to attend the emergency. Failure of which penalty of Rs 5,000/- shall be imposed on the agency. 3. The agency should quote the rates accordingly as per DPC/NGT guidelines within the municipal limits as per DPC/NGT guidelines will be the sole responsibility of the agency and nothing extra shall be paid on this account by the department. Taking permission of MCD Dhalajal/ Dumping site will be the sole responsibility of agency itself. 4. All safety measures/precautions are to be taken while doing the work. In case of any casualty, agency will be sole responsible. There will be no role of DDA in it. 5. During execution of work if any challan is received in this office from NGT, MCD/DPC/CPB, local body or any other govt. agency, the same shall be borne by the agency and if fails double the amount of challan will be recovered from the bill of agency. Nothing extra will be paid to agency on this account. 6. Rate is inclusive of all T&P required for the work and shall be arranged by the contractor itself. 7. If the agency fails to do the work on the direction of Site Staff or Engineer-in-charge by any communication means i.e. by phone, whatsapp or by Site Order Book within 24 hours then the penalty of Rs 2000/- shall be imposed for per day delay. In case of any dispute, decision of Engineer-in-charge shall be final and binding. 8. In case of any emergency, the agency shall have to deploy his team at any location under jurisdiction of DMD-II as and when directed by Engineer-in-charge. Failure of which penalty of Rs 5,000/- will be imposed and work will be forfeited. Decision of Engineer-in-charge will be final and binding. 9. While doing work if any of Drain Cover will be broken by the staff deployed by the agency then same will be replaced by the agency and no extra payment will be given in this account. 10. The agency shall submit before and after GPS enabled photographs/videos of every day of work. Failure of which penalty of Rs 500/- per day will be imposed. 11. The agency will perform the work stretchwise/roadwise except if any direction has been issued by Engineer-in-charge.							
Total in Figures						2856736.00	INR Twenty Eight Lakh Fifty Six Thousand Seven Hundred & Thirty Six Only
Quoted Rate in Figures		Less (-)		66.23%		1248679.31	INR Twelve Lakh Forty Eight Thousand Six Hundred & Seventy Nine and Paise Thirty One Only
Quoted Rate in Words		INR Twelve Lakh Forty Eight Thousand Six Hundred & Seventy Nine and Paise Thirty One Only					


Executive Engineer
 अतिरिक्त अभियंता
 11/रि. अभियंता
 ए.पी.एम.डी.-२, १/१/२०२०