



दिल्ली विकास प्राधिकरण / Delhi Development Authority
कार्यालय अधिशाषी अभियंता / O/o Executive Engineer
द्वारका रखरखाव खंड-II / Dwarka Maintenance Division -II
केन्द्रीय नर्सरी सेक्टर-5 द्वारका / Central Nursery, Sector -5, Dwarka
नई दिल्ली :- ११००७५ / New Delhi -110075
ईमेल - eedmd2@dda.org.in

No. F54(2182)/EE/DMD-2/DDA/2025-26/A/267

Dated: 11/03/2026

To

M/s Shiv Deepanshi Const. Co.
C-81A, Vishwas Park
Uttam Nagar
New Delhi-110059

Name of Work: M/o various colonies under Nazul Account-II, Dwarka Zone
Sub-Head: Cleaning and Desilting of SW Drains of MP Road No.215, 30 Mtr.
Road of Sector-22 & 23 and Metro Corridor under the jurisdiction
of SD-IV/DMD-II.

Ref: F54(2182)/EE/DMD-II/DDA/2025-26/A/205 Dated: 24.02.2026
P.G. Received on: 28.02.2026 for Rs. 1,27,172/- in the shape of Confirmation of
Deposit issued by Punjab National Bank

Dear Sir,

Your Percentage rate tender for the above-mentioned work is hereby accepted on
behalf of the Delhi Development Authority at the rates, terms & conditions given below:

Estimated Cost: Rs. 28,53,954/- (Rupees Twenty Eight Lakh Fifty Three
Thousand Nine Hundred Fifty Four Only)
Quoted/tendered: Rs.12,71,722/- (Rupees Twelve Lakh Seventy One
Thousand Seven Hundred Twenty Two only)
Accepted Amount: Rs.12,71,722/- (Rupees Twelve Lakh Seventy One
Thousand Seven Hundred Twenty Two only)

The percentage to be taken for the purpose of Clause-12 of the agreement shall 55.44%
below on the rates based on DSR- 2023.

You are requested to attend the office along with a non-judicial stamp paper worth
Rs. 100/- (Rupees Hundred Only) to complete the formal agreement within ten days from the
date of issue of this letter.

Please note that time allowed for completion of work as entered in the tender shall be
reckoned from the 10th day from the date of issue of this letter to commence the work. The
time allowed for execution of work is 180 days.

You are requested to contact AE -IV of this division and start the work immediately.

EXECUTIVE ENGINEER
DMD-II/DDA

Copy to:

1. Chief Engineer (DWK), DDA.
2. Chief Engineer (QAC), Vikas Sadan, DDA
3. S.E./DCC-1, DDA
4. The Income Tax Officer (Contractors' Cell), ITO, New Delhi.
5. Dy. Director (System) DDA with the request to e-mail the same in the website of DDA-ddatender@dda.org.in.
6. Labour Commissioner, 15, Rajpur Road, Delhi.
7. Secretary, CRB, DDA, Vikas Minar, New Delhi.
8. All Ex. Engineers, Dwarka Zone, DDA.
9. A.O(Works)-II, DDA.
10. AO(CAU)/Dwarka, DDA.
11. All AEs, H.C, AAO/DMD-II.
12. AE-IV/DMD-II, DDA, along with Schedule of Quantities & Rates.
13. Agreement copy.
14. Work File.

Janis
11/03/L-46
EXECUTIVE ENGINEER
DMD-II/DDA

Tender Inviting Authority: Delhi Development Authority

Name of Work: M/o Various Colonies Under Nazul A/C-II Dwarka Zone,
S/H:- Cleaning and Desilting of SW Drains of MP Road No. 215, 30 Mtr. road of Sector-22 & 23 and Metro Corridor under the jurisdiction of SD-IV/DMD-II

Contract No. 40/EED/DMD-2/DDA/2025-26

Name of the Bidder/ Bidding Firm / Company : M/S Shiv Deepanshi Construction Co.

Percentage BOQ

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	NUMBER #	TEXT #	Item Description	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
				Quantity	Units	Rate in P	TOTAL AMOUNT	TOTAL AMOUNT
						Rs. in P	Rs. P	In Words
1	2	3	4	5	6	7		
1			Cleaning & Desilting of peripheral and internal covered SW drain of any width & depth, including taking out dry/wet/semi wet sludge, silt and maha rubbish etc. (i/c any dead animal etc.) etc. and disposal of the excavated material for all lead & all lift/depth at Municipal dumping ground/low lying area and opening (dismissing old CC if required) & fixing of drain cover with Cement Concrete, cleaning of bell mouth, cleaning of kerb channel, removal of blockage, creating obstruction in smooth flow of drain or under water/ liquid mud including pumping out of water, if required in or under foul condition. All complete as per direction of engineer in charge (before and after GPS Photographs has to be submitted by agency) (For payment purpose, measurement of plan area of executed drain surface area).	16238.00	Sqm.	137.65	2235161.00	INR Twenty Two Lakh Thirty Five Thousand One Hundred & Sixty One Only
2			Cleaning of kerb channel of main carriageway and of service lance (wherever available) of any width, including removing of all kind of material, maha, rubbish, silt and dust etc. and disposal of the same material for all lead & all lift/depth at Municipal dumping ground/low lying area or as per direction of Engineer-in-Charge and opening and cleaning of bell mouth, removal of blockage, creating obstruction in smooth flow of water etc all complete as per direction of Engineer-in-charge (Before and after GPS Photographs has to be submitted by agency) (For payment purpose, length of kerb channel will be measured).	22310.00	metre	3.25	72508.00	INR Seventy Two Thousand Five Hundred & Eight Only
3			Cleaning of Choked Drain by Diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000litres water jetting tank capacity i/c skilled operator, supervising engineer etc. for cleaning and desilting of drain line and chamber and dechoking of drain. Dechocking and flushing of drain from one manhole to another by high pressure jetting system of 2200 PSI of depth more than 300mm.	550.00	metre	324.25	178334.00	INR One Lakh Seventy Eight Thousand Three Hundred & Thirty Eight Only
4			Making bell mouth opening/ entrance of size 100x50x50 cm for drainage pipe under footpath, including providing cement concrete 1:3:6 (1 cement: 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) for shape of bell mouth, including plastering providing and fixing Precast R.C.C./ S.F.R.C. slab including plastering with cement mortar 1:3:1 (Cement : 3 fine sand) of 6 mm thickness on exposed surface of the slab & bell mouth including centring, shuttering & neat cement punning inside the bell mouth etc. all complete.	5.00	each	3050.40	15252.00	INR Fifteen Thousand Two Hundred & Fifty Two Only
5			Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars joined with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including, lessening of joints etc. complete. : 250 mm dia. R.C.C. pipe	10.00	metre	899.80	8998.00	INR Eight Thousand Nine Hundred & Ninety Eight Only
6			Providing and placing in position 100 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M:25 grade cement concrete for RCC work, including cost of centring, shuttering, reinforcement of 8 mm dia TMT bars of Fe 500 grade @ maximum 100 mm c/c on both ways, neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick, 100 mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc including cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	93.00	Sqm.	3081.95	286621.00	INR Two Lakh Eighty Six Thousand Six Hundred & Twenty One Only
7			Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality a) Circular shape 560 mm internal diameter	10.00	each	1675.70	16757.00	INR Sixteen Thousand Seven Hundred & Fifty Seven Only
8			Providing and fixing Precast RCC/SFRC slab of cement concrete 1:3:6 (1 cement : 3 coarse Sand : 6 graded stone aggregate 20 mm nominal size) of bell mouth i/c plastering with cement mortar 1:3:1 (Cement : 3 coarse Sand) of 6mm thickness on exposed surface of slab having size 140.5x0.05 m, all complete as per direction of Engineer-in-Charge	44.00	each	774.60	34082.00	INR Thirty Four Thousand & Eighty Two Only

GST Correction factor @0.873x2770829					
Add Cl @ 3%				83125.00	
<p>Terms & Conditions:-</p> <ol style="list-style-type: none"> 1. As this work is time bound & urgent work so if required more than one team shall be mobilized by the agency in case of urgency/emergency, other than normal working hours within two hours of given instructions by Engineer-in-Charge. No extra payment shall be made for this. Failure of which penalty of Rs. 5000/- shall be imposed on the agency. 2. In case of any emergency, the agency shall have to deploy the team even in odd hours, a night hours to attend the emergency work. Failure of which penalty of Rs. 5000/- shall be imposed on the agency. 3. The agency should quote the same accordingly as same disposal within the municipal limits as per DPCC/NGT guidelines will be the sole responsibility of the agency and nothing extra shall be paid on the account of the agency. 4. All safety measurements/operations are to be taken by the agency. In case of any casualty, agency will be sole responsible. There will be no role of ODA in it. 5. During execution of work if any challan is received in the office from HQ, OD, DPCC/CPCB, local body or any other govt. agency, the same shall be borne by the agency and if fails double the amount of challan will be recovered from the bill of agency. Nothing extra will be arranged by the contractor for this account. 6. Rate is inclusive of all TSP required for the work and shall be arranged by the contractor for this account. 7. If the agency fails to do the work on the direction of Site Staff or Engineer-in-Charge by any communication means i.e. by phone, whatsapp or by Site Order Book within 24 hours then the penalty of Rs. 2000/- shall be imposed for per day delay. In case of any dispute, decision of Engineer-in-Charge shall be final and binding. 8. In case of any emergency, the agency shall have to deploy the team at any location under jurisdiction of DMD-II as and when directed by Engineer-in-Charge. Failure of which penalty of Rs. 5000/- will be imposed on the agency. 9. While doing work if any of Driver/Operator of the vehicle of every day of work, Failure of which penalty of Rs. 500/- per day will be imposed. 10. The agency shall submit before and after GPS reading by the staff deployed by the agency then same will be replaced by the agency and no extra payment will be given in this account. 11. The agency will perform the work stretch/roadside except if any direction has been issued by Engineer-in-Charge. 					
Total in Figures				2853954.00	INR Twenty Eight Lakh Fifty Three Thousand Nine Hundred & Fifty Four Only
Quoted Rate in Figures				1271721.90	INR Twelve Lakh Seventy One Thousand Seven Hundred & Twenty One Only
Quoted Rate in Words					INR Twelve Lakh Seventy One Thousand Seven Hundred & Twenty One and Paise Ninety Only
		Less (-)	85.44%		


 अशिश्वरी अभियंता
 Executive Engineer
 शा.सं.ख.सू.उ-11/दि.सि.शा.
 M.D.-21/D.D.A.
